
Solicitation Number 3-MAIN-GATE-IMPROVEMENTS-2009

Amendment #2 Attachments



NATIONAL AERONAUTICS AND SPACE ADMINISTRATION
GLENN RESEARCH CENTER
21000 BROOKPARK ROAD, CLEVELAND, OHIO 44135
February 27, 2009



BACKGROUND

This Proposed Construction Sequence lays out a plan to perform the anticipated Phase 1 construction work in a logical order that achieves the following objectives:

- a. Maintains access to the Glenn Research Center during construction
- b. Keeps construction personnel and GRC personnel segregated as much as possible.
- c. Limits the number of times that GRC staff will have to change traffic patterns.
- d. Allows the construction crews room to work.
- e. Limits cases where subsequent work might require demolition or rework to completed work.

SUMMARY OF CONSTRUCTION SEQUENCES

This Proposed Construction Sequence calls for all Phase I work to be completed in three "Sequences", labeled A, B, and C. Unless noted otherwise, it is assumed that the previous tasks are completed before a given task can be started (Pre-requisites are identified). The set of drawings that accompany this document show in graphic form the limits of work in the various sequences. In some cases, exact limit lines have some flexibility for ease of construction. Each task is assumed to include the associated placement of underground utilities in the affected area.

PHASE 1- SEQUENCE A

Sequence A contains three task areas that should be completed at the start of the project. In this case, the three tasks are somewhat independent and can be performed simultaneously.

1. TASK A1- Construct Force Main

Description: The force main piping is to be installed from the existing City of Cleveland Manhole north of Brookpark Road in front of the Building 500/501 parking lot, run west to boring location under Brookpark Road and continue south to tie-in to existing Lift Station. As installation nears the intersection of Underpass Road and existing Walcott Road, a short duration road closure of Underpass Road will be required.

Pre-Requisites: None

Road Closures: 3- Underpass Road near Buildings 500/501, Underpass Road at Walcott Road, short turn loop from southbound Walcott Road to Underpass Road

Normal GRC Entry: From existing Walcott Road to either Taylor Road or Stratton Road.

PHASE 1- SEQUENCE A (cont.)

2. Re-Open Underpass Road

Description: Once force main is run south of Underpass Road, re-open

Underpass Road

Pre-Requisites: Completion of Task A1.

Road Closures: None

Normal GRC Entry: From either existing Walcott Road or Underpass Road to

either Taylor Road or Walcott Road.

3. TASK A2- Construct Intersection of Taylor Road and Stratton Road

Description: While the connection from existing Walcott Road to Stratton Road is still intact, the intersection of Taylor Road and Walcott Road will be reconstructed. This work must leave the northern entrance to the main hangar parking lot accessible during construction. This work will also include installation of the new traffic signal system.

Pre-Requisites: None

Road Closures: 4- Southern entrance to main hangar parking lot, at entrance from existing Walcott Road to Taylor Road, At western intersection of Stratton Road and existing Walcott Road, and to the south at intersection at Taylor Road and Ames Road

Normal GRC Entry: From either existing Walcott Road or Underpass Road to Walcott Road only.

4. Re-Open Intersection of Taylor Road and Stratton Road

Description: Once Task A2 is completed, re-open just the intersection of Taylor

Road and Stratton Road.

Pre-Requisites: Completion of Task A2

Road Closures: Leave entrance from existing Walcott Road to Taylor Road

closed for Item B4.

Normal GRC Entry: From either existing Walcott Road or Underpass Road to

Walcott Road only.

5. TASK A3- Perform Soil Stabilization at site of New Gatehouse

Description: According to the findings for the Soils Report, the existing soil in the proposed area of the new Gatehouse is good soil, but it is loosely compacted. Before the site can be developed, the soil will need to be stabilized. Stabilization will require removing the soil to a depth of 10 feet in an area of the footprint of the Gatehouse plus 16 feet all around. The soil will be dried and replaced and recompacted to achieve the desired bearing capacity. This work should be done first to clear the area for development work.

Pre-Requisites: None **Road Closures:** None

Normal GRC Entry: From either existing Walcott Road or Underpass Road to

Walcott Road only.

END OF PHASE 1- SEQUENCE A

PHASE 1- SEQUENCE B

6. TASK B4- Complete Pavement at South End of New Walcott Road

Description: While the connection from existing Walcott Road to Stratton Road is still intact, complete paving work where the southern end of new Walcott Road will connect to Taylor Road. This work must keep the southern entrance to the main hangar parking lot open. The work will include installation of pop-up barriers and wrong way devices south of the new Gatehouse location. Northern extent of the pavement will stop short of the new Gatehouse location to allow room to work on the Gatehouse later.

Pre-Requisites: Completion of Task A2

Road Closures: 3- Northern entrance to main hangar parking lot, at entrance from existing Walcott Road to Taylor Road, at intersection of Taylor Road and Stratton Road.

Normal GRC Entry: From either existing Walcott Road or Underpass Road to Walcott Road only.

7. Re-Open Taylor Road

Description: Once task B4 is completed, Taylor Road can be re-opened. It will now become the primary entrance to the GRC site.

Pre-Requisites: Completion of Task B4

Road Closures: None

Normal GRC Entry: From either existing Walcott Road or Underpass Road to

Taylor Road only.

8. TASK B5- Development of Southwest Site

Description: Once Taylor Road has been re-constructed, work can begin on demolition and renovation of the southwestern portion of the site. Once completed, this work will now take the western turn of existing Walcott Road out of service permanently. The work must be staged to leave one of the two entrances to the parking lot northwest of the Administration Building accessible at all times. This can be accomplished by constructing the western portion first while leaving the east entrance in service. Once the western portion is completed, the western entrance can be re-opened, and Walcott permanently closed at the east end.

Pre-Requisites: Completion of Tasks A2 and B4

Road Closures: 5- western end of parking lot(temporary), eastern end of parking lot(temporary), intersection of Walcott Road and Ames Road (temporary), intersection of Taylor Road and Stratton Road, and the eastern connection to existing Walcott Road.

Normal GRC Entry: From either existing Walcott Road or Underpass Road to Taylor Road only.

9. Re-Open Stratton Road

Description: Once Task B5 is complete, Stratton Road can be reopened at

Taylor Road and all other road closures removed.

Pre-Requisites: Completion of Task B5

Road Closures: None

Normal GRC Entry: From either existing Walcott Road or Underpass Road to

Taylor Road only.

END OF PHASE 1- SEQUENCE B

PHASE 1- SEQUENCE C

10. TASK C6- Complete Phase 1 Pavement Work for New Walcott Road


Description: At this point, existing Walcott Road will be closed. The new construction at the intersection of Walcott Road and Brookpark Road can be completed as well as the construction of both northbound and southbound lanes of new Walcott Road to the extent indicated on the drawings. This work also includes installation of crash resistance fencing and three-cable fencing along the eastern property line.


Pre-Requisites: Completion of Phase 1, Sequences A, and B

Road Closures: 3- Both incoming and outbound lanes of Walcott Road at intersection of Brookpark Road and Walcott Road at intersection of Underpass Road. (Note: An optional fourth road closure could occur at the loop from existing Walcott Road to northbound Underpass Road).

Normal GRC Entry: From Underpass Road only to Taylor Road only.

END OF PHASE 1- SEQUENCE C AND CONCLUSION OF PHASE 1





FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675 PROJECT NAME: NASA GRC Main Gate Security Upgrade LOCATION: Brook Park, Cuyahoga Co., Ohio CLIENT: A.M. Kinney, Inc. DRILLING CO: **EBD** DRILLING METHOD: 4-1/2" O.D. SSA DRILLERS: ML GEOLOGIST: JĽ

DATE BEGUN: 04/16/08

STATION: TOTAL DEPTH: 10.0 (ft) DATE COMPLETED:

04/16/08

OFFSET:

SURFACE ELEVATION: 758.0 (ft)

WATER LEVELS:


DURING DRILLING: UPON COMPLETION:

Not Encountered Not Encountered

AFTER COMPLETION:

N/A

| | | | | | | | | |
|-------------|-----|------|----------------|---|-------------|-------|----|------|
| DEPTH | | SAM | | | | DEPTH | | FLEV |
| (ft) | NO. | TYPE | BLOWS/0.5 (ft) | N | DESCRIPTION | (ft) | W% | (ft) |



FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

PROJECT NAME: NASA GRC Main Gate Security Upgrade

LOCATION: CLIENT:

DRILLING CO:

Brook Park, Cuyahoga Co., Ohio

A.M. Kinney, Inc.

EBD

DRILLING METHOD: 4-1/2" O.D. SSA

DRILLERS: GEOLOGIST: ML JL

TOTAL DEPTH: 12.0 (ft)

DATE BEGUN: 04/16/08

DATE COMPLETED: 04/16/08

OFFSET:

SURFACE ELEVATION: 753.8 (ft)

WATER LEVELS:

STATION:

DURING DRILLING:

Not Encountered


UPON COMPLETION:

Not Encountered

AFTER COMPLETION: N/A

DEPTH SAMPLE INFORMATION DESCRIPTION (ft) BLOWS/0.5 (ft) Ν

DEPTH ELEV. (ft) (ft)



SURFACE ELEVATION: 758.4 (ft)

04/17/08

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

PROJECT NAME:

NASA GRC Main Gate Security Upgrade

LOCATION: CLIENT:

Brook Park, Cuyahoga Co., Ohio

DRILLING CO:

A.M. Kinney, Inc.

EBD

DRILLING METHOD: 4-1/2" O.D. SSA

DRILLERS: GEOLOGIST: ML JL

WATER LEVELS:

STATION:

DURING DRILLING:

DATE BEGUN: 04/17/08

TOTAL DEPTH: 15.0 (ft)

UPON COMPLETION:

Not Encountered


OFFSET:

DATE COMPLETED:

Not Encountered

AFTER COMPLETION: N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION NO. TYPE BLOWS/0.5 (ft) W% (ft) N (ft) (ft)



SURFACE ELEVATION: 751.4 (ft)

04/21/08

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

PROJECT NAME: NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

LOCATION: CLIENT:

A.M. Kinney, Inc.

DRILLING CO:

DRILLING METHOD: 4-1/2" O.D. SSA

GEOLOGIST:

DRILLERS: ML JL

WATER LEVELS:

STATION:

DURING DRILLING:

DATE BEGUN: 04/21/08

TOTAL DEPTH: 10.0 (ft)

UPON COMPLETION:

Not Encountered


Not Encountered

OFFSET:

DATE COMPLETED:

AFTER COMPLETION: N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. BLOWS/0.5 (ft) DESCRIPTION (ft) NO. TYPE Ν (ft) (ft)



SURFACE ELEVATION: 752.0 (ft)

04/21/08

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

PROJECT NAME:

NASA GRC Main Gate Security Upgrade

LOCATION: Brook Park, Cuyahoga Co., Ohio

CLIENT:

A.M. Kinney, Inc.

DRILLING CO: DRILLING METHOD: 4-1/2" O.D. SSA

DRILLERS: GEOLOGIST: ML

EBD

WATER LEVELS: **DURING DRILLING:**

STATION:

UPON COMPLETION:

DATE BEGUN: 04/21/08

TOTAL DEPTH: 10.0 (ft)

AFTER COMPLETION:


Not Encountered Not Encountered

OFFSET:

DATE COMPLETED:

N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION NO. TYPE BLOWS/0.5 (ft) (ft) W% (ft) (ft)



FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

PROJECT NAME:

NASA GRC Main Gate Security Upgrade

STATION:

DATE COMPLETED: 04/16/08

SURFACE ELEVATION: 754.3 (ft)

OFFSET:

LOCATION: CLIENT:

Brook Park, Cuyahoga Co., Ohio

A.M. Kinney, Inc.

DRILLING CO:

EBD

WATER LEVELS:

DRILLERS:

ML

DRILLING METHOD: 4-1/2" O.D. SSA

DURING DRILLING: UPON COMPLETION:

DATE BEGUN: 04/16/08

TOTAL DEPTH: 10.0 (ft)


7.0 (ft) 6.0 (ft)

GEOLOGIST:

AFTER COMPLETION:

N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION BLOWS/0.5 (ft) (ft) W% (ft) (ft)



FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675 PROJECT NAME:

NASA GRC Main Gate Security Upgrade

STATION:

DATE COMPLETED:

04/17/08

LOCATION:

Brook Park, Cuyahoga Co., Ohio

TOTAL DEPTH: 30.0 (ft)

DATE BEGUN: 04/17/08

OFFSET: SURFACE ELEVATION: 757.7 (ft)

CLIENT:

A.M. Kinney, Inc.

DRILLING CO:

EBD

WATER LEVELS:

23.5 (ft)

DRILLERS:

ML

DRILLING METHOD: 4-1/2" O.D. SSA

DURING DRILLING:


UPON COMPLETION:

17.0 (ft)

GEOLOGIST: JL AFTER COMPLETION:

N/A

| DEPTH | | SAM | PLE INFORMATION | | 1 | Incorul | 1 ' | E. E |
|-------|-----|------|-----------------|---|-------------|---------|-----|-------|
| | | | | | i | DELIH | 1 | LLEV. |
| (ft) | NO. | TYPE | BLOWS/0.5 (ft) | N | DESCRIPTION | (ft) | W% | (ft) |
| \ '' | l | | | | |). (II) | | (11,) |



20.5 (ft)

04/16/08

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675 DATE BEGUN: 04/16/08 DATE COMPLETED: NASA GRC Main Gate Security Upgrade PROJECT NAME: STATION: OFFSET: LOCATION: SURFACE ELEVATION: 757.8 (ft) Brook Park, Cuyahoga Co., Ohio TOTAL DEPTH: 25.5 (ft) CLIENT: A.M. Kinney, Inc.

DRILLING CO: EBD WATER LEVELS:

DRILLING METHOD: 4-1/2" O.D. SSA **DURING DRILLING:** DRILLERS: ML

UPON COMPLETION: 20.0 (ft) GEOLOGIST: AFTER COMPLETION: JL N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION NO. TYPE BLOWS/0.5 (ft) (ft) Ν (ft) (ft) 0.0 TOPSOIL: 10 (in) 8.0 7 SS 3-3-4 16 A-6b: Brown to gray/brown, medium stiff SILTY CLAY, some sand, little gravel and slitstone / sandstone / slag fragments, odorless, moderate to weak reaction to HCI, 755 moist. (FILL) SS 8 2 1-3-5 19 5.0 5.0 A-6a: Gray/brown, medium stiff SILT AND CLAY, little sand, trace gravel and slitstone / sandstone / shale 3 SS 7 2-3-4 16 fragments, odorless, no to weak reaction to HCL, homogeneous soil structure, moist. (Possible Fill) 750 7 4 SS 2-3-4 19 10.0 745 5 SS 2-2-3 5 19 15.0 SS 2-2-3 5 6 20 20.0 20.5 A-4a: Gray, stiff SANDY SILT, little clay, trace gravel and siltstone / wood fragments, odorless, weak reaction to HCI, wet. 735 SS 5-5-7 12 **7T** 22 24.5 25.0 A-6a: <continued>, TERMINATION DEPTH: 25.5 (FT)

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675 PROJECT NAME:

NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

DATE BEGUN: 04/17/08 STATION: TOTAL DEPTH: 20.0 (ft)

DATE COMPLETED: 04/17/08

OFFSET: SURFACE ELEVATION: 755.7 (ft)

LOCATION: CLIENT:

DRILLING CO:

DRILLERS:

GEOLOGIST:

A.M. Kinney

EBD

DRILLING METHOD: 4-1/2" O.D. SSA

ML JL


WATER LEVELS:

DURING DRILLING: UPON COMPLETION:

AFTER COMPLETION:

5.5 (ft) 17.0 (ft) N/A

| | DEPTH | | SAM | PLE INFORMATION | | | DEPTH | | ELEV. |
|---|-------|-----|------|-----------------|---|-------------|---------|----|---------|
| | (ft) | NO. | TYPE | BLOWS/0.5 (ft) | N | DESCRIPTION | (ft) | W% | (ft) |
| - | | | | | | | <u></u> | | <u></u> |



FIELD BOREHOLE LOG

B-4

PROJECT NUMBER: JL07675

PROJECT NAME:

NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

A.M. Kinney EBD

DRILLING METHOD: 4-1/2" O.D. SSA

DRILLING CO:

LOCATION:

CLIENT:

STATION:

DATE COMPLETED: 04/18/08

OFFSET:

TOTAL DEPTH: 15.0 (ft)

DATE BEGUN: 04/18/08

SURFACE ELEVATION: 751.4 (ft)

WATER LEVELS:

DURING DRILLING:

Not Encountered

| DRILLE GEOLG | | : | ML JL | | UPON COMPLETION: Not Encoun AFTER COMPLETION: N/A | tered | | |
|-----------------|-----|------|----------------|-----|--|--------|--------|-------|
| DEPTH | | SAMF | PLE INFORMATIO | N | | DEPTH | l L | ELEV. |
| (ft) | NO. | TYPE | BLOWS/0.5 (ft) | N | DESCRIPTION | (ft) | W% | (ft) |
| 0.0 | | | | | | | - | |
| 0.0 | | | | | TOPSOIL: 12 (in). | 3 | | |
| | | SS | 4-4-4 | 8 | A-6a: Brown, medium stiff to stiff SILT AND CLAY, some sand, trace gravel and sandstone / siltstone / slag fragments, odorless, moderate to weak reaction to HCl, | 1.0 | 17 | 750 |
| | 2 | ss | 2-4-6 | 10 | moist. (FILL) | | 22 | |
| 5.0 | 3 | ST | REC: 11 (in) | | A-4a: Brown, very stiff to hard SANDY SILT, little gravel | 5.0 | 17 | |
| 1 | 4 | ss | 8-13-14 | 27 | and siltstone / sandstone fragments, odorless, no to weak reaction to HCl, homogeneous soil structure, moist. | | 13 | 745 |
| 10.0 — | 5 | ss | 9-14-22 | 36 | A control of the cont | 27,171 | 13 | |
| | 6 | ss | 22-33-31 | 50+ | | 11.9 | 10 | 740 |
| | 7 | ss | 16-24-26 | 50 | DxSH: DECOMPOSED SHALE, gray. | | 10 | |

TERMINATION DEPTH: 15.0 (FT)

FIELD BOREHOLE LOG

STATION:

PROJECT NUMBER: JL07675

PROJECT NAME: NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

DATE BEGUN: 04/18/08

TOTAL DEPTH: 19.5 (ft)

DATE COMPLETED: 04/18/08

OFFSET:

SURFACE ELEVATION: 753.2 (ft)

LOCATION: CLIENT:

DRILLING CO:

DRILLERS:

A.M. Kinney

EBD

ML

DRILLING METHOD: 4-1/2" O.D. SSA

WATER LEVELS: DURING DRILLING:

UPON COMPLETION:

Not Encountered Not Encountered

| GEOL | OGIST | : | JL | | AFTER COMPLETION: N/A | countered | | |
|--------|-------|-----------|----------------|-----|--|-----------|----|------------|
| DEPTH | 1 | 1 | PLE INFORMATIO | V | | DEPTH | | ELEV. |
| (ft) | NO. | TYPE | BLOWS/0.5 (ft) | N | DESCRIPTION | (ft) | W% | (ft) |
| 0.0 — | | ········· | | | | | | |
| • | 1 | ss | 3-5-9 | 14 | TOPSOIL: 7 (in) A-6b: Brown, stiff to hard SILTY CLAY, little sand, trace | 0.6 | 17 | L |
| 5.0 — | 2 | ss | 6-12-13 | 25 | gravel and sandstone / siltstone / chert fragments, odorless, moderate reaction to HCl, homogeneous soil structure, moist. (Possible Decomposed Shale) | | 16 | 750 |
| - | 3 | ss | 10-19-20 | 39 | | | 16 | |
| 10.0 — | 4 | ss | 9-17-21 | 38 | | | 12 | 745 |
| 15.0 | 5. | SS | 20-21-30 | 50+ | DxSh: DECOMPOSED SHALE, gray/brown. | 11.0 | 10 | - 740 |
| | 6 | ss | 38-53/6 | 50+ | | | 8 | - 735 - |

TERMINATION DEPTH: 19.5 (FT)

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675 PROJECT NAME: LOCATION:

NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

DATE BEGUN: 04/21/08 STATION: TOTAL DEPTH: 14.8 (ft)

DATE COMPLETED: 04/21/08

OFFSET: SURFACE ELEVATION: 739.8 (ft)

CLIENT: DRILLING CO:

DRILLERS:

GEOLOGIST:

A.M. Kinney

EBD

DRILLING METHOD: 4-1/2" O.D. SSA

ML JL

WATER LEVELS:


DURING DRILLING:

UPON COMPLETION:

Not Encountered Not Encountered

AFTER COMPLETION: N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION (ft) NO. TYPE BLOWS/0.5 (ft) W% Ν (ft) (ft)



740

11

FIELD BOREHOLE LOG

B-7 PROJECT NUMBER: JL07675 DATE BEGUN: 04/21/08 DATE COMPLETED: 04/21/08 PROJECT NAME: NASA GRC Main Gate Security Upgrade STATION: OFFSET: LOCATION: Brook Park, Cuyahoga Co., Ohio TOTAL DEPTH: 15.0 (ft) SURFACE ELEVATION: 752.8 (ft) CLIENT: A.M. Kinney DRILLING CO: EBD WATER LEVELS: DRILLING METHOD: 4-1/2" O.D. SSA Not Encountered DURING DRILLING: DRILLERS: ML **UPON COMPLETION:** Not Encountered GEOLOGIST: JL AFTER COMPLETION: N/A DEPTH SAMPLE INFORMATION DEPTH ELEV. DESCRIPTION (ft) NO. TYPE BLOWS/0.5 (ft) N (ft) W% (ft) 0.0 TOPSOIL: 6 (in) 1 SS 2-3-8 11 17 A-6a: Brown, stiff to very stiff SILT AND CLAY, odorless, strong reaction to HCI, homogeneous soil structure, 750 2 SS 7-11-14 25 18 5.0 3 ST REC: 12 (in). 21 A-7-6: Brown, hard CLAY and silt, trace sand, moderate reaction to HCI, homogeneous soil structure, moist. 4 SS 8-20-26 46 6.0 14 (Possible decomposed shale or siltstone) DxST: DECOMPOSED SILTSTONE, gray. 745 5 SS 9-22-22 44 13

TERMINATION DEPTH: 15.0 (FT)

10.0

15.0

6

SS

24-30-44

50+

FIELD BOREHOLE LOG

PROJECT NUMBER: JL07675

NASA GRC Main Gate Security Upgrade

Brook Park, Cuyahoga Co., Ohio

STATION:

DATE BEGUN: 04/21/08

DATE COMPLETED: 04/21/08

OFFSET:

TOTAL DEPTH: 10.0 (ft)

SURFACE ELEVATION: 735.6 (ft)

CLIENT:

LOCATION: A.M. Kinney

DRILLING CO:

EBD

WATER LEVELS:

DRILLERS:

GEOLOGIST:

PROJECT NAME:

ML JL


DRILLING METHOD: 4-1/2" O.D. SSA

DURING DRILLING: UPON COMPLETION: Not Encountered Not Encountered

AFTER COMPLETION:

N/A

SAMPLE INFORMATION DEPTH DEPTH ELEV. DESCRIPTION NO. TYPE BLOWS/0.5 (ft) W% (ft) Ν (ft) (ft)



| Project: N. | ASA GRC M | ain Gate Se | Project: NASA GRC Main Gate Security Project | | | | _ | ABORAT | JL07675 LABORATORY TEST SUMMARY | s T SUMMA | | | | | | | | Client: | Client: A. M. Kinney, Inc. |
|-------------|-----------|-------------|--|------------------|----------------------|-------------------------------|----------|--------|------------------------------------|--------------|----------|------------------------------------|------------|------|-------|----------|------------------|--------------|----------------------------|
| Boring | Sample | Depth | Moisture | | Perc | Percent Passing (by weight) | ng (by w | eight) | 7/2/2008 | ~ | Particle | Particle Size Distribution Sand | istributio | Ę | | Attert | Atterberg Limits | iits | TOGO |
| Number | Number | (tt) | Content (%) | 3/8" | # | #10 | #40 | #100 | #200 | Gravel | Cor. | Fine | Silt | Clay | Fines | 러 | , പ | ᆸ | Classification |
| R-1 | - | 1.0 | 5 | 67 | 91 | 82 | 29 | 90 | 56 | ~ | 15 | /- | 30 | 56 | 56 | 32 | 21 | d d | A-63 |
| | 2 (1) | 2.0 | 19 | Brown, SILTY | | CLAY | | | | | | | | | | | | | Visual |
| | m | 3.5 | 15 | 100 | 98 | 95 | 87 | 80 | 75 | 2 | 8 | 12 | | ı | 75 | 37 | 19 | 18 | A-6b |
| | 4 | 6.0 | 15 | Brown, | Brown, SILTY CLAY | ,LAY | | | | | | | | | | | | | Visual |
| | to. | ద చ | 9 | Brown, | Brown, SILTY CLAY | :LAY | | | | | | | | | | | | | Visual |
| R-2 | ₩- | 1.0 | 19 | 86 | 26 | 63 | 85 | 74 | 29 | 7 | 80 | 18 | 1 | 1 | 29 | 29 | 8 | ~ | A-6a |
| | 2 | 3.5 | 20 | 100 | 67 | 91 | 78 | 29 | 63 | 6 | 13 | 15 | ω — | 32 | 63 | 33 | 18 | 4 | A-6a |
| | က | 6.0 | 23 | Brown, SILT Al | SILT AN | ND CLAY | | | | | | | | | | | | | Visual |
| | 4 | 8.5 | 22 | Brown, SILT Al | SILTAN | ND CLAY | | | | | | | | | | | | | Visual |
| | £ (1) | 10.0 | 21 | 96 | 95 | 93 | 88 | 83 | 79 | 7 | c) | o | 30 | 49 | 79 | 4 | 19 | 21 | A-7-6 |
| | | | | | | | | | | | | | | | | | | | |
| R-3 | 4 | 0. | 21 | Brown, | Brown, SILT AND CLAY | D CLAY | | | | | | | | | | | | | Visual |
| | 2 | ය. ස | 16 | 96 | 96 | 92 | 86 | 78 | 75 | 80 | 9 | An- | 1 | ŀ | 75 | 1 | | } | A-6a |
| | က | 5.0 | 17 | 66 | 98 | 96 | 89 | 83 | 79 | 4 | 7 | 10 | 31 | 48 | 79 | 36 | 19 | 17 | A-6b |
| | 4 | 6.0 | 16 | 66 | 26 | 93 | 83 | 92 | 76 | 7 | 10 | 7 | į | 1. | 76 | 35 | 21 | 14 | A-6a |
| | S | 8,5 | 16 | Light brown, SII | own, SIL | LT AND CLAY | LAY | | | | | | | | | | | | Visual |
| | 9 | 11.0 | 19 | 100 | 100 100 | 100 | 100 | 66 | 65 | 0 | 0 | 35 | } | 1 | 65 | Š | <u>م</u> | œ. | A-4a |
| | 7 | 13.5 | 20 | Brown, | Brown, SILT AND CLAY | D CLAY | | | | | | | | | | | | | Visual |
| R-4 | _ | 1.0 | 18 | 66 | 26 | 95 | 89 | 84 | \$1 | 5 | 9 | 80 | ł | ŧ | 81 | 36 | 20 | 16 | A-6b |
| | 2 | 3.5 | 16 | 66 | 98 | 95 | 88 | 83 | 79 | 5 | 7 | 6 | 43 | 36 | 79 | 23 | 17 | 9 | A-4a |
| | က | 0.0 | 13 | Brown, | SILT AN | Brown, SILT AND CLAY | | | | | | | | | | | | | Visual |
| | 4 | 8.5 | 1 | Brown a | nd gray, | Brown and gray, SANDY SILT | SILT | | | | | | | | | | | | Visual |
| R-5 | _ | 1.0 | 16 | 66 | 96 | 92 | 84 | 77 | 72 | ø | œ | 12 | 29 | 43 | 72 | 31 | 19 | 4 | A-6a |
| | 2 | 3.5 | 18 | 100 | 66 | 96 | 93 | 89 | 86 | 2 | 2 | 7 | | 1 | 86 | 31 | 9 | 11 | A-6a |
| | en = | 6.0 | 27 | Brown, | Brown, SILT AND CLAY | DCLAY | ē | | | | | | | | | | | | Visual |
| | 4 | α.υ | - | Brown a | nd gray, | Brown and gray, SILT AND CLAY | D CLAY | | | | | | | | | | | | Visual |
| R-6 | <u>_</u> | 1.0 | 13 | 95 | 85 | 68 | 47 | 37 | 33 | 32 | 73 | 14 | *** | ŀ | 33 | ŧ | ì | 1 | A-2-6 |
| | 2 (1) | 2.0 | 12 | 26 | 67 | 94 | 84 | 78 | 74 | Đ | 10 | 10 | 37 | 37 | 74 | 27 | 16 | * | A-6a |
| | ಌ | 3.5 | 17 | 66 | 26 | 94 | 87 | 82 | 62 | 9 | 7 | 0 0 | 27 | 52 | 79 | 37 | 21 | 16 | A-6b |
| | 4 1 | 6.0 | 16 | Brown, | Brown, SILT AND CLAY | DCLAY | | | | | | | | | | | | | Visual |
| | ç. | 50 57 | 10 | Gray, SI | Gray, SILT AND CLAY | CLAY | | | | | | | | | | | | | Visual |

Page 1
J&L Laboratories
Testing Summary (rev. 10/2003)

Notes: (1) Shelby tube obtained from offset boring

| iert | |
|----------|---|
| ă | • |
| Security | |
| Gate | |
| Main | |
| GRC | |
| NASA | |
| Project: | |

| | • | | | | | | : 1 | | 7/2/2000 | 4/2/2000 | | Particle Size Distribution | Distribut | noi | | | | | |
|------------------|--|-------------------|-------------------------|-----------------------|---|---|-------------------|-----------|----------|----------|-------------|----------------------------|-----------|----------------|-------|-------|------------------|------------|------------------------|
| Boring Number | Sample Number | Depth (ft) | Moisture Content (%) | 3/8" | Percent | Percent Passing (by weight) #4 #10 #40 #10 | (by weig #40 # | 0 | #200 | Gravel | Sa Cor. | Sand Fine | Silt | Clay | Fines | Atter | Atterberg Limits | mits PI | ODOT Classification |
| B-1 | ۵. | 1.0 | 16 | Brown, S | Brown, SILT AND C | CLAY | 2 | ç | 7 | ţ | c | ç | | | 7 | 66 | ć | 7 | Visual |
| | 4 67 | . o | - 4 | Brown S | S | > | D. | 7. | 3 | | D. | 7 | l | l | 5 | ò | <u> </u> | ŗ | Visital |
| | > ব | 8.0 | - <u>~</u> 25 | 100 | 97 | | 89 | 83 | 78 | 5 | 9 | 11 | 1 | I | 78 | 37 | 20 | 1 | A-6b |
| | Ð | 10.0 | 23 | 98 | | 94 | 88 | 82 | 77 | 9 | 9 | 11 | 1 | ì | 7.7 | 1 | 1 | ı | A-6b |
| | Ģ | 13.5 | 25 | Brownish | Brownish gray, SIL1 | TY CLAY | | | | | | | | | | | | | Visual |
| | 2 | 18.0 | 28 | 100 | 0 | 100 1 | 100 | 66 | 98 | 0 | 0 | 2 | 1 | ı | 98 | 52 | 26 | 25 | A-7-6 |
| | 80 | 19.7 | 18 | Gray, CLAY | ΑY | | | | | | | | | | | | | | Visual |
| | 91 | 23.5 | 24 | 66 | 98 | | | 67 | 96 | 7 | 0 | 7 | 72 | 24 | 96 | £ | ď | <u>a</u> | A-4b |
| | 9B 10 | 24.5 28.5 | - | 97 Dark gra | 97 86 64 42 30 Dark gray, DECOMPOSED SILTSTONE | 64 / | 42 SILTST(| 30 ONE | 25 | 36 | 22 | 17 | 1 | I | 25 | ı | t e | Į. | A-1-b Visual |
| B-2 | 4 | 0 | 16 | Brown, S | Brown, SILTY CLAY | | | | | | | | | | | | | | Visual |
| ı | ۰ ۵ | 3.5 | 19 | 86 | 93 | 2 | 72 | 62 | 58 | 13 | 15 | 4 | 1 | ı | 58 | 35 | 19 | 16 | A-6b |
| | ෆ | 6.0 | 16 | Grayish | , SI | NDC | AY | | | | | | | | | | | | Visual |
| | 4 | 8.5 | 19 | 94 | | 88 | 81 | 80 | 9/ | 12 | 7 | rO | ı | ı | 9/ | 34 | 20 | 14 | A-6a |
| | 52 | 13.5 | 19 | Grayish | | T AND CLAY | .ΑΥ | | | | | | | | | | | | Visual |
| | 9 | 18,5 | 20 | Grayish | Grayish brown, SIL | T AND CLAY | | | | | | | | | | | | | Visual |
| | 77 | 24.0 | 22 | 86 | 26 | | 93 | 65 | 47 | 4 | က | 46 | 32 | 1 5 | 47 | Ž | S S | Ž | A-4a |
| | 7.8 | 25.0 | 12 | Gray, SII | Gray, SILT AND CLAY | ΑY | | | | | | | | | | | | | Visual |
| B-3 | 4 | 1.0 | 16 | Brown, S | Brown, SILTY CLAY | _ | | | | | | | | | | | | | Visual |
| | 2 | 3.5 | 15 | 96 | 91 | 83 | 72 | 90 | 56 | 17 | | 16 | ŧ | 1 | 56 | ! | ŀ | 1 | A-6b |
| | 8 | 6.0 | 25 | 97 | 93 | | | 63 | 58 | - | 17 | 14 | I | 1 | 58 | 39 | 19 | 20 | A-6b |
| | 4 | 8,5 | 21 | Brownish | Brownish gray, SILT | TY CLAY | | | | | | | | | | | | | Visual |
| | 5 | 13.0 | 23 | 66 | 86 | 95 8 | 38 | 81 | 77 | IJ | 7 | 7 | i. | ł | 7.7 | 40 | 20 | 20 | A-6b |
| | 9 / | 15.0 18.5 | 23 46 | Brownist Gray, SII | Brownish gray, SILTY CLAY Gray, SILTY CLAY | ry Clay | | | | | | | | | | | | | Visual Visual |
| B-4 | + | 1.0 | 17 | 66 | 86 | 95 | 92 | 76 | 7.1 | ĸ | o, | ć. | *** | ı | 71 | 32 | 6 | 12 | A-6a |
| | 2 | 3,5 | 22 | Brown, S | O. | | | <u>;</u> | | | | | | | | | | | Visual |
| | 3 | 5.0 | 17 | 66 | 62 | | 77 | 99 | 58 | 10 | 13 | 49 | 1 | ł | 58 | 23 | 2 | 2 | A-4a |
| | 4 | 6.3 | 13 | Brown, S | Brown, SANDY SILT | _ | | | | | | | | | | | | | Visual |
| | ις | 80 80 | 13 | 66 | 96 | 89 7 | | 68 | 63 | # | 13 | 13 | 1 | Į | 63 | ì | ŧ | ŧ | A-4a |
| | 9 | 11.0 | 10 | Gray, DE | Gray, DECOMPOSED SHALE | ED SHAL | ш | | | | | | | | | | | | Visual |
| | 7 | 13.5 | 10 | Gray, DE | COMPOS | ED SHAL | ш | | | | | | | | | | | | Visual |
| B-5 | | 1.0 | 17 | Brown, S | Brown, SILTY CLAY | _ | | | | | | | | | | | | | Visual |
| | 2 | 3,5 | 16 | 66 | 96 | 3 | 85 | 80 | 9/ | 7 | œ | တ | 1 | ŀ | 92 | 38 | 21 | 13 | A-6b |
| | က | 6.0 | 16 | Brown, S | Brown, SILTY CLAY | | | | | | | | | | | | | | Visual |
| | 4 | 8,5 | 12 | Brown/gr | Brown/gray, SILTY (| CLAY | | | | | | | | | | | | | Visual |
| | 5 | 13.5 | 10 | Gray/bro | Gray/brown, DECOMPOSED SHALE | MPOSEL | SHALE | 111 | | | | | | | | | | | Visual |
| 100 | Constitute on the sample of | 18.5 | œ | Gray/bro | wn, DECOI | MPOSEL | SHALE | het. | | | ٠ | | | | | | | | Visual |
| e deptt | Tables = on and day commissed Sample deaths indicate for of sample interval | of sample inte | je/us | | | | | | | | | | | | | | | | Page 2 |
| | Constant of the Constant of th | The profession of | | | | | | | | | | | | | | | | | 181 I ahoratories |

| 2 | | ا۔ | ٠ | | | | | | | | | | | | | | | |
|--|---------------------------------|----------------|----------------|--------------|----------------|----------------|----------------|---------------|----------------|----------------|-------|---------------|---------------|----------------|-------------|----------------|---------------------------------|---------------------------------|
| Client: A. M. Kinney, Inc. | 0000 | Classification | Visual | A-6a | Visual | Visual | Visual | Visual | Visual | Visual | A-7-6 | Visual | Visual | Visual | A-6a | Visual | Visual | Visual |
| Client | nits | ۵ | | 1 | | | | | | | 20 | | | | | | | |
| | Atterberg Limits | 집 | | *** | | | | | | | 24 | | | | 18 | | | |
| | Atte | = | | ŀ | | | | | | | 44 | | | | 29 | | | |
| | | Fines | | 73 | | | | | | | 26 | | | | 80 | | | |
| | noi | Clay | | ł | | | | | | | ì | | | | 1 | | | |
| | Distribul | SIII | | ı | | | | | | | 1 | | | | | | | |
| | Particle Size Distribution Sand | Fine | | 4 | | | | | | | 7 | | | | ø | | | |
| ARY | | Cor. | | 10 | | | | | | | _ | | | | æ | | | |
| 5 ST SUMN | 80 | Gravel | | 9 | | | | | | | 0 | | | | 4 | | | |
| JL07675 LABORATORY TEST SUMMARY | 7/2/2008 | #200 | | 73 | | | | | | | 26 | | | | 90 | | | |
| BORA | ight) | #100 | | 11 | | | | ш | | | 98 | ш | ш | ш | 83 | | TONE | TONE |
| 2 | Percent Passing (by weight) | #40 | | 84 | | | | SED SILTSTONE | | | 66 | SED SILTSTONE | SED SILTSTONE | SED SILTSTONE | 88 | | SILTS | SILTS |
| | it Passin | #10 | CLAY | 94 | CLAY | CLAY | CLAY | SED SIL | CLAY | CLAY | 100 | SED SIL | SED SIL | SED SIL | 96 | CLAY | IPOSEI | APOSEI |
| | Percer | ## | | 98 | T AND C | T AND C | T AND C | | T AND C | TANDC | 100 | COMPO | | COMPO | 96 | T AND C | Dark gray, DECOMPOSED SILTSTONE | Dark gray, DECOMPOSED SILTSTONE |
| | | 3/8" | Gray, SILT AND | 100 | Gray, SILT AND | Gray, SILT AND | Gray, SILT AND | Gray, DECOMP(| Gray, SILT AND | Gray, SILT AND | 100 | Gray, DECOMPC | Gray, DECOMP(| Gray, DECOMPC | 100 | Gray, SILT AND | Dark gra | Dark gra |
| Project: NASA GRC Main Gate Security Project | Moisture | Content (%) | 40 | 10 | 10 | 12 | 15 | 1 | 17 | 18 | 21 | 14 | 13 | *** | 12 | 12 | **** | 1 |
| iin Gate Sec | Depth | (E) | 0.1 | 3.0 | 3.5 | 6.0 | 8.5 | 13.5 | 1.0 | 3,5 | 5.0 | 6.0 | 8.5 | 13,5 | 1.5 | 3.5 | 0.9 | 8.5 |
| SA GRC M | Sample | Number | ₩. | 2 | ന | 4 | 5 | ග | | 2 | ೮ | 4 | လ | 9 | _ | 2 | က | 4 |
| Project: NA | Boring | Number | B-6 | | | | | ٠ | B-7 | | | | | | B-8 | | | |

Direct Shear Test of Soil Under Consolidated Drained Conditions ASTM (D-3080)

Project: NASA GRC Main Gate Security Upgrade

Testing Date: 6/17/2008

A.M.

Tested by:

Project No: JL.07675

Client: A. M. Kinney, Inc.

| SOIL CLASSIFICATION | (ODOT) | A-6b | A-7-6 |
|----------------------------|-------------|-------|-------|
| ANGLE OF INTERNAL FRICTION | (degree) | 27.9 | 19.4 |
| COHESION | (bst) | 552 | 1248 |
| DRY DENSITY | (bcf) | 106.4 | 114.8 |
| WET DENSITY | (bcf) | 128.7 | 134.9 |
| MOISTURE | CONTENT (%) | 21.0 | 17.5 |
| DEPTH | (ft.) | 8.0 | 5.0 |
| BORING | No. | B-1 | B-7 |

PROJECT: NASA GRC Main Gate Security Upgrade CLIENT: A.M. Kinney

J&L PROJ. No.: JL07675

UNCONFINED COMPRESSIVE STRENGTH OF COHESIVE SOILS (ASTM D-2166)

| SOIL CLASSIFICATION (Visual) | A-6b | A-6b | A-4a | A-7-6 |
|---|----------------|--------|--------|--------|
| CLASS | | 4 | | 4, |
| ESTIMATED COHESION (psf) | 1268 | 672 | 2155 | 1677 |
| UNCONFINED COMPRESSIVE STRENGTH (psf) | 2535.2 | 1344.8 | 4309.6 | 3354.9 |
| PERCENT STRAIN AT FAILURE | <u>ස</u> තු | 14.4 | 9.1 | 6.1 |
| DRY DENSITY (pcf) | 106.4 | 108.3 | 109.9 | 114.8 |
| WET DENSITY (pcf) | 128.7 | 131.0 | 131.0 | 134,9 |
| SAMPLE MOISTURE DEPTH CONTENT (ft.) (%) | 21.0 | 21.0 | 19.2 | 17.5 |
| SAMPLE DEPTH (ft.) | හ හ | 14.2 | 5,5 | 5.2 |
| BORING No. | 8-1 | B-3 | B-4 | B-7 |

TESTED BY: AM

TESTING DATE: 06/10/08

| Nimber Bumber Ivo | |
|--------------------|-----------|
| Boring Sample Samp | ole Depth |

 $K_{20^{\circ}C} = 1.60E-08 \text{ cm/sec}$


Test Conditions:

| Permeant Liquid | Back Pressure | Hydraulic Gradient | Consolidat Max (psi) | | Total Test | ii Voletin Killing aan ku o maayan mis siddi. |
|---------------------------|------------------|-----------------------|-------------------------|---|------------|---|
| De-aired/De-ionized water | 50 psi | 5 psi | 6 | 2 | 1920 | 4.2 |

Initial Sample Data:

| Moisture | Saturation | Diameter | Length | Area | Wet Density | Dry Density |
|----------|------------|----------|--------|-------|-------------|-------------|
| (%) | (%) | (cm) | (cm) | (cm²) | (pcf) | (pcf) |
| 21.1 | 100.0 | 7.209 | 6.371 | 40.81 | 131.3 | 108.4 |

| Reading | Time (h:m) | Chamber | Upper | Lower | Flow | K _{ze} (cm/s) |
|---------|------------|---------|-------|-------|------|------------------------|
| 1 | 0:00 | 14.3 | 24.7 | 0.3 | 0.0 | |
| 2 | 0:15 | 14.2 | 24.6 | 0.4 | 0.1 | 4.93E-08 |
| 3 | 0:30 | 14.2 | 24.5 | 0.5 | 0.2 | 4.93E-08 |
| 4 | 1:00 | 14.1 | 24.4 | 0.6 | 0.3 | 3.70E-08 |
| 5 | 2:00 | 14.0 | 24.2 | 0.8 | 0.5 | 3.08E-08 |
| 6 | 4:00 | 14.0 | 24.0 | 1.1 | 0.8 | 2.31E-08 |
| 7 | 8:00 | 13.9 | 23.5 | 1.6 | 1.3 | 1.93E-08 |
| 8 | 24:00 | 14.2 | 21.7 | 3.6 | 3.2 | 1.62E-08 |
| 9 | 32:00 | 14.3 | 20.7 | 4.6 | 4.2 | 1.60E-08 |



| Number | Number | Type | (ft) |
|--------|--------|--------|-------|
| Boring | Sample | Sample | Depth |

 $K_{20^{\circ}C} = 4.71E-08 \text{ cm/sec}$

Test Conditions:


| | | e tout in a residence to M | erication days a communication | 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 1 | 4 | of commence of the commence of the | |
|-----|----------------------------|----------------------------|--------------------------------|--|--|--|--|
| | Permeant Liquid | Back | Hydraulic | Consolida | tion Stress | Total Test | Total |
| | | | | 119311000 MORE WAS 1000 AND AND AND ADDRESS. | ra avida toria kewada sulkofishi i | Garage (Carlos Carlos Garages) (Carlos Carlos Carlo | Maria Para da Calendra da La Calendra da Maria D |
| : | | Pressure | Gradient | Max (psi) | Min (psi) | Time (min) | Flow (cc) |
| | De-aired/De-ionized water | 50 psi | 5 ooi | c | A CONTRACTOR OF THE PARTY OF TH | 4000 | AND COMPANY OF STREET OF STREET OF STREET OF STREET |
| - 1 | De-alled/De-lottized Water | ou psi | 5 psi | O | 4 | 1920 | 13.9 |

Initial Sample Data:

| Moisture | Saturation | Diameter | Length | Area | Wet Density | Dry Density |
|----------|------------|----------|--------|-------|-------------|-------------|
| (%) | (%) | (cm) | (cm) | (cm²) | (pcf) | (pcf) |
| 14.8 | 97.4 | 7.173 | 5.454 | 40.41 | 135.2 | |

| | Moisture (%) | Saturation (%) | Diameter (cm) | Length (cm) | Area (cm²) | Wet Density (pcf) | Dry Density (pcf) |
|---|--------------|-------------------|------------------|----------------|---------------|----------------------|----------------------|
| L | 17.4 | 100.0 | 7.124 | 5.475 | 39.86 | 139.7 | 119.0 |

| Reading | Time (h:m) | Chamber | Upper | Lower | Flow | K ₂₀ (cm/s) |
|---------|------------|---------|-------|-------|------|------------------------|
| 1 | 0:00 | 11.5 | 24.4 | 0.9 | 0.0 | |
| 2 | 0:15 | 11.5 | 24.3 | 1.1 | 0.1 | 6.51E-08 |
| 3 | 0:30 | 11.5 | 24.1 | 1.2 | 0.3 | 6.51E-08 |
| 4 | 1:00 | 11.5 | 23.9 | 1.5 | 0.6 | 5.96E-08 |
| 5 | 2:00 | 11.4 | 23.4 | 2.0 | 1.1 | 5.69E-08 |
| 6 | 4:00 | 11.6 | 22.5 | 3.0 | 2.0 | 5.42E-08 |
| 7 | 8:00 | 11.5 | 20.6 | 4.9 | 3.9 | 5.29E-08 |
| 8 | 24:00 | 11.9 | 13.8 | 12.0 | 10.9 | 4.90E-08 |
| 9 | 32:00 | 12.1 | 10.8 | 15.1 | 13.9 | 4.71E-08 |



| Boring Number | | | Depth (ft) |
|------------------|---|----|---------------|
| B-1 | 1 | SS | 8.0'~10.0' |

 $K_{20^{\circ}C} = 4.02E-08 \text{ cm/sec}$

Test Conditions:


| Permeant Liquid | Back Pressure | Hydraulic Gradient | PAGE WELLWENGERSELDT | kay 6 mengangan palaman Palah T | Total Test Time (min) | |
|---------------------------|------------------|-----------------------|----------------------|---------------------------------|-----------------------|------|
| De-aired/De-ionized water | 50 psi | 5 psi | 6 | 2 | 2880 | 17.4 |

Initial Sample Data:

| Moisture (%) | Saturation (%) | Diameter (cm) | Length (cm) | Area (cm²) | Wet Density (pcf) | Dry Density (pcf) |
|-----------------|----------------|------------------|----------------|---------------|-------------------|----------------------|
| 16.4 | 98.5 | 7.183 | 5.738 | 40.52 | 140.2 | 120.4 |

| Moisture | Saturation | Diameter | Length | Area | Wet Density | Dry Density |
|----------|------------|----------|--------|-------|-------------|-------------|
| (%) | (%) | (cm) | (cm) | (cm²) | (pcf) | (pcf) |
| 17.9 | 100.0 | 7.232 | 5.767 | 41.08 | 139.4 | 118.2 |

| Reading | Time (h:m) | Chamber | Upper | Lower | Flow | K ₂₀ (cm/s) |
|---------|------------|---------|-------|-------|------|------------------------|
| 1 | 0:00 | 10.4 | 24.8 | 0.4 | 0.0 | |
| 2 | 1:00 | 10.1 | 24.3 | 1.0 | 0.6 | 6.10E-08 |
| 3 | 2:00 | 10.3 | 23.8 | 1.5 | 1.1 | 5.96E-08 |
| 4 | 4:00 | 10.4 | 22.9 | 2.5 | 2.0 | 5.54E-08 |
| 5 | 8:00 | 10.4 | 21.4 | 4.1 | 3.6 | 4.92E-08 |
| 6. | 24:00 | 11.0 | 16.0 | 9.5 | 9.0 | 4.13E-08 |
| 7 | 48:00 | 11.3 | 7.4 | 17.8 | 17.4 | 4.02E-08 |



| Test Pit | Sample | Sample | Depth |
|----------|-------------|--------|-----------|
| R-6 | Number 1 | SS | 3.0'-3.5' |

 $K_{20^{\circ}C} = 2.07E-08 \text{ cm/sec}$

Test Conditions:


| Permeant Liquid | Back Pressure | Hydraulic Gradient | Consolidat Max (psi) | ali kalenda kalendari da Kalendari | Total Test | 🐞 til 100 avan engan 4974 i 1-81 |
|---------------------------|------------------|-----------------------|-------------------------|------------------------------------|------------|----------------------------------|
| De-aired/De-ionized water | 50 psi | 5 psi | 6 | 2 | 5760 | 19.8 |

Initial Sample Data:

| Moisture | Saturation | Diameter | Length | Area | Wet Density | Dry Density |
|----------|------------|----------|--------|-------|-------------|-------------|
| (%) | (%) | (cm) | (cm) | (cm²) | (pcf) | (pcf) |
| 9.5 | 97.4 | 7.225 | 5.032 | 40.99 | 139.5 | |

| Moisture | Saturation | Diameter | Length | Area | Wet Density | Dry Density |
|----------|------------|----------|--------|-------|----------------|-------------|
| (%) | (%) | (cm) | (cm) | (cm²) | (pcf) | (pcf) |
| 12.0 | 100.0 | 7.125 | 5.075 | 39.87 | 145 <i>.</i> 4 | 129.8 |

| Reading | Time (h:m) | Chamber | Upper | Lower | Flow | K ₂₀ (cm/s) |
|---------|------------|---------|-------|-------|------|------------------------|
| 1 | 0:00 | 16.8 | 24.6 | 0.5 | 0.0 | |
| 2 | 0:15 | 16.7 | 24.5 | 0.7 | 0.2 | 6.03E-08 |
| 3 | 0:30 | 16.7 | 24.4 | 0.8 | 0.3 | 5.02E-08 |
| 4 | 1:00 | 16.6 | 24.3 | 1.0 | 0.4 | 4.02E-08 |
| 5 | 2:00 | 16.6 | 24.0 | 1.3 | 0.7 | 3.52E-08 |
| 6 | 4:00 | 16.6 | 23.6 | 1.8 | 1.2 | 2.89E-08 |
| 7 | 8:00 | 16.6 | 22.6 | 2.8 | 2.2 | 2.70E-08 |
| 8 | 24:00 | 16.9 | 19.0 | 6.5 | 5.8 | 2.43E-08 |
| 9 | 32:00 | 17.0 | 17.4 | 8.2 | 7.5 | 2.34E-08 |
| 10 | 96:00 | 17.4 | 4.9 | 20.3 | 19.8 | 2.07E-08 |
| 0 | | | | | | |



ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES ALL REPORTS, PLANS, SPECIFICATIONS, COMPDIENT FILES, FIELD DATA, NOTES AND OTHER DOCUMENTS AND INSTRUMENTS PREPARED BY A.M. KINNEY, INC. AS INSTRUMENTS OF SERVICE SHALL REMAIN THE PROPERTY OF A.M. KINNEY, INC. A.M. KINNEY, INC. SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT REV. NO.




A.M. Kinney, Inc.

Founded 1929

150 E. 4th STREET CINCINNATI, OHIO 45202 513-421-2265 800-AMK-3682 FAX 513-421-2264

| DESIGN | DRAWN | SCALE | DATE | JOB NO. |
|--------|-------|----------|----------|---------|
| TRR | TRR | AS NOTED | 11/20/06 | 03370 |
| | | | | |



| | LEGEND | | | | | | |
|------|-------------------------------|--|--|--|--|--|--|
| ITEM | TUBULAR | ROLL FORMED | | | | | |
| 1 | 2½"OD @ 3.65#/LF | 3½"x3½" ◎ 3.65#/LF | | | | | |
| 2 | 2"OD @ 2.72#/LF | 2.25" H-COL @ 3.26#/LF OR 2.25" C-COL @ 2.64#/LF | | | | | |
| 3 | 3/8"¢ TRUSS ROD & TIGHTENER | 3/8"ø TRUSS ROD & TIGHTENER | | | | | |
| 4 | APPROVED CAPS | NOT REQUIRED | | | | | |
| (5) | 15/8" BRACE @ 2.27#/LF | 1.25"x1.625" @ 1.35#/LF | | | | | |
| 6 | 15/8" OD @ 2.27#/LF | 1.25"x1.625" @ 1.35#/LF | | | | | |
| 7 | 3/16"x3/4" FLAT STRETCHER BAR | NOT REQUIRED | | | | | |
| 8 | BRACE BAND & TENSION BAND | NOT REQUIRED | | | | | |
| 9 | BARBED WIRE | BARBED WIRE | | | | | |
| 10 | BARBED WIRE ARM | BARBED WIRE ARM | | | | | |
| 11 | ½"ø CABLE (SEE NOTE) | ½"ø CABLE (SEE NOTE) | | | | | |

TO CRASH RESISTANT CAPABILITIES—1/2" & CABLE SHALL BE ADDED AS SHOWN AND APPROPRIATELY ANCHORED.

| | | | | DRAWING TITLE | DRAWING NUMBER |
|----|------|-----------|----|----------------------------|-------------------|
| | | | | CHAIN LINK FENCE DETAIL | C_007 |
| | | | | I LINGE DETAIL | |
| NO | DATE | REVISIONS | BY | | FILE sk-fence.dwg |