



STRUCTURAL TESTS, INSPECTIONS, AND OBSERVATIONS

1. PER SECTION 1704 OF CBC 2007, THE FOLLOWING ITEMS SHALL BE INSPECTED AND TESTED BY A DEPUTY INSPECTOR.
2. ALL TESTS AND INSPECTIONS SHALL BE PERFORMED BY A SPECIAL INSPECTOR PER CBC SECTION 1704. THE SPECIAL INSPECTOR SHALL BE EMPLOYED BY THE OWNER, BUT NOT BY THE CONTRACTOR OR ANY OTHER PERSON RESPONSIBLE FOR THE WORK.
3. THE SPECIAL INSPECTOR SHALL BE A QUALIFIED (LICENSED) PERSON WHO SHALL DEMONSTRATE COMPETENCE TO THE SATISFACTION OF THE BUILDING OFFICIAL, FOR INSPECTION OF THE PARTICULAR TYPE OF CONSTRUCTION OR OPERATION REQUIRING SPECIAL INSPECTION.

| LIST OF SPECIAL INSPECTION  | YES | NO | N/A |
|---|-----|----|-----|
| FOUNDATION:   |     |    |     |
| A. GRADING AND FILLING AND CUT OPERATION PER SOILS REPORT   | X   |    |     |
| B. FILL MATERIAL ACCEPTANCE TEST, COMPACTION CONTROL  | X   |    |     |
| BEARING CAPACITY OF COMPACTED FILL  | X   |    |     |
| CONCRETE:   |     |    |     |
| A. DURING THE TAKING OF TEST SPECIMENS  | X   |    |     |
| PLACING OF REINFORCED CONCRETE  | X   |    |     |
| B. SHOTCRETE  |     |    | X   |
| C. BOLT INSTALLED IN CONCRETE   | X   |    |     |
| REINFORCING STEEL & PRE-STRESSING:  |     |    |     |
| A. DURING PLACING OF REINFORCING, TENDONS & PRE-STRESSED STEEL  | X   |    |     |
| B. DURING STRESSING OF POST TENSIONED CONCRETE  |     |    | X   |
| ELONGATE JACKING FORCE LIFT-OFF FOR EVERY 18TH TENDON   |     |    |     |
| C. SAMPLE AND TEST BAR STEEL & POST-TENSION CABLE   | X   |    |     |
| STRUCTURAL MASONRY:   |     |    |     |
| A. DURING PREPARATION AND TAKING OF PRISM OR TEST SPECIMENS   | X   |    |     |
| B. PLACING OF ALL MASONRY UNITS, REINFORCEMENT, GROUTING AND MASONRY PRISM TEST   | X   |    |     |
| STRUCTURAL STEEL:   |     |    |     |
| A. MILL REPORTS AND IDENTIFICATION OF STEEL (AFADAVIT OF COMPLIANCE)  | X   |    |     |
| B. SAMPLING AND TESTING OF SPECIMEN   | X   |    |     |
| WELDING:  |     |    |     |
| A. ALL STRUCTURAL WELDING (INCLUDES DECKING AND WELDED STUDS)   | X   |    |     |
| B. ULTRASONIC TESTING OF FULL PENETRATION WELD CONNECTIONS AT MOMENT FRAMES, BRACED FRAMES, BEAM SPLICES, AND FIELD WELDS | X   |    |     |
| C. STRUCTURAL LIGHT GAGE METAL FRAME WELDING  | X   |    |     |
| D. REINFORCING STEEL WELDING PER CBC 1704.4.2   | X   |    |     |
| BOLT:   |     |    |     |
| A. HIGH STRENGTH BOLT A325SC & A490SC (TENSION VERIFICATION)  | X   |    |     |
| B. HIGH STRENGTH BOLT A325N & A490N (SNUG CONTACT OF PLYS)  | X   |    |     |
| C. EXPANSION/ ADHESIVE ANCHORS IN CONCRETE OR MASONRY INSTALLATION AND TESTING  | X   |    |     |
| D. ANCHOR BOLTS AT CONCRETE WALLS AND BRACED FRAMES. (BOLT INSTALLATION AND CONCRETE PLACEMENT)                           | X   |    |     |

TABLE 1704.3: REQUIRED VERIFICATION AND INSPECTION OF STEEL CONSTRUCTION

| VERIFICATION AND INSPECTION   | CONTINUOUS | PERIODIC | REFERENCED STANDARD a.  | IBC REFERENCE |
|---|------------|----------|---|---------------|
| 1. MATERIAL VERIFICATION OF HIGH-STRENGTH BOLTS, NUTS AND WASHERS:  |            |          |   |               |
| A. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.   | ---        | X        | APPLICABLE ASTM MATERIAL SPECIFICATIONS: AISC 360, SECTION A3.3 | ---           |
| B. MANUFACTURER'S CERTIFICATE OF COMPLIANCE REQUIRED.   | ---        | X        | ---   | ---           |
| 2. INSPECTION OF HIGH-STRENGTH BOLTING:   |            |          |   |               |
| A. BEARING TYPE CONNECTIONS.  | ---        | X        | ---   | ---           |
| B. SLIP-CRITICAL CONNECTIONS.   | X          | X        | AISC 360, SECTION M2.5  | 1704.3.3      |
| 3. MATERIAL VERIFICATION OF STRUCTURAL STEEL:   |            |          |   |               |
| A. IDENTIFICATION MARKINGS TO CONFORM TO ASTM STANDARDS SPECIFIED IN THE APPROVED CONSTRUCTION DOCUMENTS.   | ---        | ---      | ASTM A 6 OR ASTM A 568  | 1708.4        |
| B. MANUFACTURERS' CERTIFIED MILL TEST REPORTS.  | ---        | ---      | ASTM A 6 OR ASTM A 568  | ---           |
| 4. MATERIAL VERIFICATION OF WELD FILLER MATERIALS:  |            |          |   |               |
| A. IDENTIFICATION MARKINGS TO CONFORM TO AWS SPECIFICATION IN THE APPROVED CONSTRUCTION DOCUMENTS.  | ---        | ---      | AISC 360, SECTION A3.5  | ---           |
| B. MANUFACTURER'S CERTIFICATE OF COMPLIANCE REQUIRED.   | ---        | ---      | ---   | ---           |
| 5. INSPECTION OF WELDING:   |            |          |   |               |
| A. STRUCTURAL STEEL:  | ---        | ---      | ---   | ---           |
| 1) COMPLETE AND PARTIAL PENETRATION GROOVE WELDS.   | X          | ---      | ---   | ---           |
| 2) MULTIPASS FILLET WELDS   | X          | ---      | ---   | ---           |
| 3) SINGLE-PASS FILLET WELDS > 5/16"   | X          | ---      | AWS D1.1  | 1704.3.1      |
| 4) SINGLE-PASS FILLET WELDS <= 5/16"  | ---        | X        | ---   | ---           |
| 5) FLOOR AND ROOF DECK WELDS.   | ---        | X        | AWS D1.3  | ---           |
| B. REINFORCING STEEL:   | ---        | ---      | ---   | ---           |
| 1) VERIFICATION OF WELDABILITY OF REINFORCING STEEL OTHER THAN ASTM A 706   | ---        | X        | ---   | ---           |
| 2) REINFORCING STEEL-RESISTING FLEXURAL AND AXIAL FORCES IN INTERMEDIATE AND SPECIAL MOMENT FRAMES, AND BOUNDARY ELEMENTS OF SPECIAL REINFORCED CONCRETE SHEAR WALLS AND SHEAR REINFORCEMENT. | X          | ---      | AWS D1.4<br>ACI 318: 3.5.2                                      | ---           |
| 3) SHEAR REINFORCEMENT.   | X          | ---      | ---   | ---           |
| 4) OTHER REINFORCING STEEL.   | ---        | X        | ---   | ---           |
| 6. INSPECTION OF STEEL FRAME JOINT DETAILS FOR COMPLIANCE WITH APPROVED CONSTRUCTION DOCUMENTS:   |            |          |   |               |
| A. DETAILS SUCH AS BRACING AND STIFFENING.  | ---        | ---      | ---   | ---           |
| B. MEMBER LOCATIONS   | ---        | ---      | ---   | ---           |
| C. APPLICATION OF JOINT DETAILS AT EACH CONNECTION  | ---        | ---      | ---   | ---           |

FOR SI: 1 INCH= 25.4 MM.

a. WHERE APPLICABLE, SEE ALSO SECTION 1707.1, SPECIAL INSPECTION FOR SEISMIC RESISTANCE

TABLE 1704.4: REQUIRED VERIFICATION AND INSPECTION OF CONCRETE CONSTRUCTION

| VERIFICATION AND INSPECTION   | CONTINUOUS | PERIODIC | REFERENCED STANDARD a.                       | IBC REFERENCE               |
|---|------------|----------|--|-----------------------------|
| 1. INSPECTION OF REINFORCING STEEL, INCLUDING PRESTRESSING TENDONS, AND PLACEMENT.  | ---        | X        | ACI 318: 3.5, 7.1-7.7                        | 1913.4                      |
| 2. INSPECTION OF REINFORCING STEEL WELDING IN ACCORDANCE WITH TABLE 1704.3, ITEM 5B.  | ---        | ---      | AWS D1.4<br>ACI 318: 3.5.2                   | ---                         |
| 3. INSPECT BOLTS TO BE INSTALLED IN CONCRETE PRIOR TO AND DURING PLACEMENT OF CONCRETE WHERE ALLOWABLE LOADS HAVE BEEN INCREASED.   | X          | ---      | ---  | 1911.5                      |
| 4. VERIFYING USE OF REQUIRED DESIGN MIX.  | ---        | X        | ACI 318: CH. 4, 5.2-5.4                      | 1904.2.2,<br>1913.2, 1913.3 |
| 5. AT THE TIME FRESH CONCRETE IS SAMPLED TO FABRICATE SPECIMENS FOR STRENGTH TESTS, PERFORM SLUMP AND AIR CONTENT TESTS, AND DETERMINE THE TEMPERATURE OF THE CONCRETE.           | X          | ---      | ASTM C 172<br>ASTM C 31<br>ACI 318: 5.6, 5.8 | 1913.10                     |
| 6. INSPECTION OF CONCRETE AND SHOTCRETE PLACEMENT FOR PROPER APPLICATION TECHNIQUES.  | X          | ---      | ACI 318: 5.9, 5.10                           | 1913.6, 1913.7,<br>1913.8   |
| 7. INSPECTION FOR MAINTENANCE OF SPECIFIED CURING TEMPERATURE AND TECHNIQUES.   | ---        | X        | ACI 318: 5.11-5.13                           | 1913.9                      |
| 8. INSPECTION OF PRESTRESSED CONCRETE:  |            |          |  |                             |
| A. APPLICATION OF PRESTRESSING FORCES.  | X          | ---      | ACI 318: 18.20<br>ACI 318: 18.18.4           | ---                         |
| B. GROUTING OF BONDED PRESTRESSING TENDONS IN THE SEISMIC- FORCE-RESISTING SYSTEM.  | X          | ---      | ---  | ---                         |
| 9. ERECTION OF PRECAST CONCRETE MEMBERS.  | ---        | X        | ACI 318: CH. 16                              | ---                         |
| 10. VERIFICATION OF IN-SITU CONCRETE STRENGTH, PRIOR TO STRESSING OF TENDONS IN post tensioned CONCRETE AND PRIOR TO REMOVAL OF SHORES AND FORMS FROM BEAMS AND STRUCTURAL SLABS. | ---        | X        | ACI 318: 6.2                                 | ---                         |
| 11. INSPECT FRAMEWORK FOR SHAPE, LOCATION AND DIMENSIONS OF THE CONCRETE MEMBER BEING FORMED  | ---        | X        | ACI 318: 6.1.1                               | ---                         |

FOR SI: 1 INCH= 25.4 MM.

a. WHERE APPLICABLE, SEE ALSO SECTION 1707.1, SPECIAL INSPECTION FOR SEISMIC RESISTANCE

TABLE 1704.5.3: LEVEL 2 SPECIAL INSPECTION

| INSPECTION TASK  | FREQUENCY OF INSPECTION       | PERIODICALLY DURING TASK LISTED | REFERENCE FOR CRITERIA     |
|--|-------------------------------|---------------------------------|----------------------------|
|  | CONTINUOUS DURING TASK LISTED | PERIODICALLY DURING TASK LISTED | IBC SECTION                |
| 1. FROM THE BEGINNING OF MASONRY CONSTRUCTION, THE FOLLOWING SHALL BE VERIFIED TO ENSURE COMPLIANCE:   |                               |                                 | ACI 530/ASCE 6/ TMS 402 a. |
| A. PROPORTIONS OF SITE- PREPARED MORTAR, GROUT AND PRESTRESSING GROUT FOR BONDED TENDONS   | ---                           | X                               | ---                        |
| B. PLACEMENT OF MASONRY UNITS AND CONSTRUCTION OF MORTAR JOINTS  | ---                           | X                               | ---                        |
| C. PLACEMENT OF REINFORCEMENT, CONNECTORS AND PRESTRESSING TENDONS AND ANCHORAGES.   | ---                           | X                               | ---                        |
| D. GROUT SPACE PRIOR TO GROUTING.  | X                             | ---                             | ---                        |
| E. PLACEMENT OF GROUT.   | X                             | ---                             | ---                        |
| F. PLACEMENT OF PRESTRESSING GROUT.  | X                             | ---                             | ---                        |
| 2. THE INSPECTION PROGRAM SHALL VERIFY:  |                               |                                 | ---                        |
| A. SIZE AND LOCATION OF STRUCTURAL ELEMENTS.   | ---                           | X                               | ---                        |
| B. TYPE, SIZE, AND LOCATION OF ANCHORS, INCLUDING OTHER DETAILS OF ANCHORAGE OF MASONRY TO STRUCTURAL MEMBERS, FRAMES OR OTHER CONSTRUCTION. | X                             | ---                             | ---                        |
| C. SPECIFIED SIZE, GRADE AND TYPE OF REINFORCEMENT.  | ---                           | X                               | ---                        |
| D. WELDING OF REINFORCING BARS   | X                             | ---                             | ---                        |
| E. PROTECTION OF MASONRY DURING COLD WEATHER (TEMPERATURE BELOW 40°F) OR HOT WEATHER (TEMPERATURE ABOVE 90°F).                               | ---                           | X                               | ---                        |
| F. APPLICATION AND MEASUREMENT OF PRESTRESSING FORCE.  | X                             | ---                             | ---                        |
| 3. PREPARATION OF ANY REQUIRED GROUT SPECIMENS, MORTAR SPECIMENS AND/OR PRISMS SHALL BE OBSERVED.  | X                             | ---                             | ---                        |
| 4. COMPLIANCE WITH REQUIRED INSPECTION PROVISIONS OF THE CONSTRUCTION DOCUMENTS AND THE APPROVED SUBMITTALS SHALL BE VERIFIED.               | ---                           | X                               | ---                        |

FOR SI: \*C= (°F-32)/1.8.

a. THE SPECIFIC STANDARDS REFERENCED ARE THOSE LISTED IN CHAPTER 35 OF 2007 IBC

TABLE 1704.7: REQUIRED VERIFICATION AND INSPECTION OF SOILS (BY GEOTECHNICAL ENGINEER).

| VERIFICATION AND INSPECTION TASK   | CONTINUOUS DURING TASK LISTED | PERIODICALLY DURING TASK LISTED |
|--|-------------------------------|---------------------------------|
| 1. VERIFY MATERIALS BELOW FOOTINGS ARE ADEQUATE TO ACHIEVE THE DESIGN BEARING CAPACITY.                              | ---                           | X                               |
| 2. VERIFY EXCAVATIONS ARE EXTENDED TO PROPER DEPTH AND HAVE REACHED PROPER MATERIAL.                                 | ---                           | X                               |
| 3. PERFORM CLASSIFICATION AND TESTING OF CONTROLLED FILL MATERIALS   | ---                           | X                               |
| 4. VERIFY USE OF PROPER MATERIALS' DENSITIES AND LIFT THICKNESSES DURING PLACEMENT AND COMPACTION OF CONTROLLED FILL | X                             | ---                             |
| 5. PRIOR TO PLACEMENT OF CONTROLLED FILL, OBSERVE SUBGRADE AND VERIFY THAT SITE HAS BEEN PREPARED PROPERLY.          | ---                           | X                               |

TABLE 1704.8: REQUIRED VERIFICATION AND INSPECTION OF PILE FOUNDATIONS

| VERIFICATION AND INSPECTION TASK   | CONTINUOUS DURING TASK LISTED | PERIODICALLY DURING TASK LISTED |
|--|-------------------------------|---------------------------------|
| 1. VERIFY PILE MATERIALS, SIZES AND LENGTHS COMPLY WITH THE REQUIREMENTS.  | X                             | ---                             |
| 2. DETERMINE CAPACITIES OF TEST PILES AND CONDUCT ADDITIONAL LOAD TESTS, AS REQUIRED.  | X                             | ---                             |
| 3. OBSERVE DRIVING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH PILE.  | X                             | ---                             |
| 4. VERIFY PLACEMENT LOCATIONS AND PLUMBNESS, CONFIRM TYPE AND SIZE OF HAMMER, RECORD NUMBER OF BLOWS PER FOOT OF PENETRATION, DETERMINE REQUIRED PENETRATIONS TO ACHIEVE DESIGN CAPACITY, RECORD TIP AND BUTT ELEVATIONS AND DOCUMENT ANY PILE DAMAGE. | X                             | ---                             |
| 5. FOR STEEL PILES, PERFORM ADDITIONAL INSPECTIONS IN ACCORDANCE WITH SECTION 1704.3.  | ---                           | ---                             |
| 6. FOR CONCRETE PILES AND CONCRETE-FILLED PILES, PERFORM ADDITIONAL INSPECTIONS IN ACCORDANCE WITH SECTION 1704.4.   | ---                           | ---                             |
| 7. FOR SPECIALTY PILES, PERFORM ADDITIONAL INSPECTIONS AS DETERMINED BY THE REGISTERED DESIGN PROFESSIONAL IN RESPONSIBLE CHARGE.  | ---                           | ---                             |
| 8. FOR AUGERED UNGRADED PILES AND CAISSON PILES, PERFORM INSPECTIONS IN ACCORDANCE WITH SECTION 1704.2.  | ---                           | ---                             |

TABLE 1704.9: REQUIRED VERIFICATION AND INSPECTION OF PIER FOUNDATIONS

| VERIFICATION AND INSPECTION TASK  | CONTINUOUS DURING TASK LISTED | PERIODICALLY DURING TASK LISTED |
|---|-------------------------------|---------------------------------|
| 1. OBSERVE DRILLING OPERATIONS AND MAINTAIN COMPLETE AND ACCURATE RECORDS FOR EACH PIER.  | X                             | ---                             |
| 2. VERIFY PLACEMENT LOCATIONS AND PLUMBNESS, CONFIRM PIER DIAMETERS AND WELL DIAMETERS (IF APPLICABLE), LENGTHS, EMBEDMENT INTO BEDROCK (IF APPLICABLE) AND ADEQUATE END BEARING STRATA CAPACITY. | X                             | ---                             |
| 3. FOR CONCRETE PIERS, PERFORM ADDITIONAL INSPECTIONS IN ACCORDANCE WITH SECTION 1704.4.  | ---                           | ---                             |
| 4. FOR MASONRY PIERS, PERFORM ADDITIONAL INSPECTIONS IN ACCORDANCE WITH SECTION 1704.5.   | ---                           | ---                             |

4. (1705.3) SPECIAL SEISMIC RESISTANCE REQUIREMENTS:

- A. THE SEISMIC-FORCE RESISTING SYSTEMS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY D, E, OR F IN ACCORDANCE WITH SECTION 1613.
- B. DESIGNATED SEISMIC SYSTEMS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY D, E, OR F.
- C. THE FOLLOWING ADDITIONAL SYSTEMS AND COMPONENTS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY C:

- C.1. HEATING, VENTILATION, AND AIR-CONDITIONING (HVAC) DUCTWORK CONTAINING HAZARDOUS MATERIALS AND ANCHORAGE OF SUCH DUCTWORK.
- C.2. PIPING SYSTEMS AND MECHANICAL UNITS CONTAINING FLAMMABLE, COMBUSTIBLE OR HIGHLY TOXIC MATERIALS.
- C.3. ANCHORAGE OF ELECTRICAL EQUIPMENT USED FOR EMERGENCY OR STANDBY POWER SYSTEMS.

- D. THE FOLLOWING ADDITIONAL SYSTEMS AND COMPONENTS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY D:

- D.1. SYSTEMS REQUIRED FOR SEISMIC DESIGN CATEGORY C
- D.2. EXTERIOR WALL PANELS AND THEIR ANCHORAGE.
- D.3. SUSPENDED CEILING SYSTEMS AND THEIR ANCHORAGE.
- D.4. ACCESS FLOORS AND THEIR ANCHORAGE.
- D.5 STEEL STORAGE RACKS AND THEIR ANCHORAGE, WHERE THE IMPORTANCE FACTOR IS EQUAL TO 1.5 IN ACCORDANCE W/ SECTION 15.5.3 OF ASCE 7.

- E. THE FOLLOWING ADDITIONAL SYSTEMS AND COMPONENTS IN STRUCTURES ASSIGNED TO SEISMIC DESIGN CATEGORY E OR F:

- E.1 SYSTEMS REQUIRED FOR SEISMIC DESIGN CATEGORIES C AND D.
- E.2 ELECTRICAL EQUIPMENT

5. (1705.4.2) SPECIAL WIND INSPECTION REQUIREMENTS:

- A. ROOF CLADDING AND ROOF FRAMING CONNECTIONS

- B. WALL CONNECTIONS TO ROOF AND FLOOR DIAPHRAGMS AND FRAMING.




















- C. ROOF AND FLOOR DIAPHRAGM SYSTEMS, INCLUDING COLLECTORS, DRAG STRUTS AND BOUNDARY ELEMENTS.

- D. VERTICAL WINDFORCE-RESISTING SYSTEMS, INCLUDING BRACED FRAMES, MOMENT FRAMES AND SHEAR WALLS.

- E. WINDFORCE-RESISTING SYSTEM CONNECTIONS TO THE FOUNDATION.

- F. FABRICATION AND INSTALLATION OF SYSTEMS OR COMPONENTS REQUIRED TO MEET THE IMPACT-RESISTANCE REQUIREMENTS OF SECTION 1609.1.2.





| PROJECT STATUS                   |             |                                    |      |
|----------------------------------|-------------|------------------------------------|------|
| PRELIMINARY-NOT FOR CONSTRUCTION |             |                                    |      |
| ISSUE                            | DATE        | DESCRIPTION                        |      |
| 1                                | 10/20/2008  | 30% PRICING                        |      |
| 2                                | 11/07/2008  | 30% DESIGN REVISION                |      |
| 3                                | 12/12/2008  | 60% INTERNAL QA/QC & COST ESTIMATE |      |
| 4                                | 12/19/2008  | 60% PRE-FINAL, NASA REVIEW         |      |
| 5                                | 02/16/2009  | 90% QA/QC & COST ESTIMATE          |      |
| MARK                             | DATE        | DESCRIPTION                        |      |
| DRAWN                            | J NAGANO    |                                    |      |
| DESIGNED                         | J LIVERMORE |                                    |      |
| CHECKED                          | N. SHAH     |                                    |      |
| PROJECT                          |             |                                    |      |
| REQUESTOR                        |             |                                    |      |
| QA/QC                            |             |                                    |      |
| SAFETY                           |             |                                    |      |
| SUPERVISOR                       |             |                                    |      |
| SIZE                             | CAGE CODE   | A232-0800-                         | S003 |
| SCALE                            | INDEX       |                                    |      |















S007 SCALE: 3/4" = 1'-0"



S007 SCALE: 1 : 1

S007 SCALE: 3/4" = 1'-0"

S007 SCALE: 3/4" = 1'-0"




S007 SCALE: 3/4" = 1'-0"

|      |        |     |
|------|--------|-----|
| S007 | SCALE: | 1 : |
|------|--------|-----|

S007 SCALE: 3/4" = 1'-0"

S007 SCALE: 3/4" = 1'-0"



S007 SCALE: 3/4" = 1'-0"


|      |        |       |
|------|--------|-------|
| S007 | SCALE: | 1 : 1 |
|------|--------|-------|


S007 SCALE: 3/4" = 1'-0"


S007 SCALE: 1" = 1'-0"

S007 SCALE: 3/4" = 1'-0"






|                |              |                                    |  |            |      |     |
|----------------|--------------|------------------------------------|--|------------|------|-----|
| PROJECT STATUS |              | PRELIMINARY-NOT FOR CONSTRUCTION   |  |            |      |     |
| ISSUE          |              |                                    |  |            |      |     |
| 1              | 10/20/2008   | 30% PRICING                        |  |            |      |     |
| 2              | 11/07/2008   | 30% DESIGN REVISION                |  |            |      |     |
| 3              | 12/12/2008   | 60% INTERNAL QA/QC & COST ESTIMATE |  |            |      |     |
| 4              | 12/19/2008   | 60% PRE-FINAL, NASA REVIEW         |  |            |      |     |
| 5              | 02/16/2009   | 90% QA/QC & COST ESTIMATE          |  |            |      |     |
| MARK           |              | DATE                               | DESCRIPTION  |            |      |     |
| DRAWN          | J. NAGANO    | DATE                               | <div><div>Ames Research Center<br/>Moffett Field, California</div><div>N232 COLLABORATIVE SUPPORT FACILITY</div><div>PARTIAL FOUNDATION PLAN<br/>NORTH WING</div></div> |            |      |     |
| DESIGNED       | J. LIVERMORE | DATE                               |  |            |      |     |
| CHECKED        | N. SHAH      | DATE                               |  |            |      |     |
| PROJ.MGR       |              | DATE                               |  |            |      |     |
| REQUESTOR      |              | DATE                               |  |            |      |     |
| QA/QA          |              | DATE                               |  |            |      |     |
| SAFETY         |              | DATE                               |  |            |      |     |
| SUPERVISOR     |              | DATE                               |  |            |      |     |
|                |              | SIZE<br>D                          | CAGE CODE<br>25307   | A232-0800- | S211 | REV |
|                |              | SCALE                              | INDEX  | SHEET      | OF   |     |








KEY PLAN


BLDG. NORTH  
True North

SCALE: 3/32" = 1'-0"

0' 4' 12' 24' 42'-8"







|                |              |  |           |            |      |
|----------------|--------------|--|-----------|------------|------|
| PROJECT STATUS |              | PRELIMINARY-NOT FOR CONSTRUCTION   |           |            |      |
| ISSUE          |              |  |           |            |      |
| 1              | 10/20/2008   | 30% PRICING  |           |            |      |
| 2              | 11/07/2008   | 30% DESIGN REVISION  |           |            |      |
| 3              | 12/12/2008   | 60% INTERNAL QA/QC & COST ESTIMATE   |           |            |      |
| 4              | 12/19/2008   | 60% PRE-FINAL, NASA REVIEW   |           |            |      |
| 5              | 02/16/2009   | 90% QA/QC & COST ESTIMATE  |           |            |      |
|                |              |  |           |            |      |
| MARK           | DATE         | DESCRIPTION  |           |            |      |
| DRAWN          | J. NAGANO    |  <p><b>Ames Research Center</b><br/>Moffett Field, California</p> <p>N232 COLLABORATIVE SUPPORT FACILITY</p> <p><b>PARTIAL SECOND FLOOR<br/>FRAMING PLAN NORTH WING</b></p> |           |            |      |
| DESIGNED       | J. LIVERMORE |  |           |            |      |
| CHECKED        | N. SHAH      |  |           |            |      |
| PROJ.MGR       |              |  |           |            |      |
| REQUESTOR      |              |  |           |            |      |
| RQA            |              |  |           |            |      |
| SAFETY         |              |  |           |            |      |
| SUPERVISOR     |              |  |           |            |      |
|                |              | SIZE   | CAGE CODE |            | REV  |
|                |              | D  | 25307     | A232-0800- | S221 |
|                |              | SCALE  | INDEX     | SHEET      | OF   |








- NOTES:
- SEE SHEET S001 AND S002 FOR GENERAL NOTES, SYMBOLS AND ABBREVIATIONS.
  - SEE SHEETS S003 THRU S007 FOR TYPICAL DETAILS.
  - CENTERLINE OF W COLUMNS AT GRID LINE, TYPICAL UNO.
  - FOR METAL DECK SECTION PROPERTIES & WELDING REQUIREMENTS, SEE DETAIL 8 S007
  - PROVIDE 3/4"x4.5" TALL HEADED STUDS FOR ALL BEAMS AT 1'-0" O.C. TYPICAL UNO.
  - INDICATES FULL MOMENT CONNECTION PER TYPICAL DETAIL 12 S005
  - INDICATES TYPICAL MOMENT CONNECTION PER DETAIL 16 S005
  - C=3/4" INDICATES BEAM CAMBER.
  - W16x INDICATES FULL HEIGHT SHEAR TAB PER 12 S004
  - INDICATES BOTTOM FLANGE BRACE PER TYPICAL DETAIL 6 S007, EQUALLY SPACED ALONG BEAM SPAN TYP. U.N.O.
  - INDICATES DRAG CONNECTION PER TYPICAL DETAIL 15 S004
  - CONTRACTOR TO VERIFY ALL DIMENSIONS RELATED TO ELEVATOR.
  - FOR VERTICAL BRACING ELEVATIONS, SEE SHEET S-501.
  - SEE SHEET S211 & S212 FOR COLUMN SIZES WHICH EXTEND TO FOUNDATION. COLUMNS WITH SIZES NOTED ON THIS SHEET, BEGINS ABOVE THIS FLOOR BEAM TOP OF STEEL LEVEL.
  - TOP OF STEEL ELEVATION = 26'-6" U.N.O., T.O. O.W.J.=26'-11" U.N.O.
  - OPEN WEB STEEL JOISTS SHALL BE DESIGNED IN ACCORDANCE W/ THE MINIMUM DESIGN LOADS INDICATED IN THE O.W.J. LOADING DIAGRAM, THIS SHEET.
  - \* INDICATES T.O.S.=26'-11"
  - FOR EDGE OF DECK DIMENSIONS, REFER TO ARCHITECTURAL DRAWINGS.






1 OWJ LOADING DIAGRAM  
S231 NOT TO SCALE



| PROJECT STATUS |              |                                    | PRELIMINARY-NOT FOR CONSTRUCTION |     |
|----------------|--------------|------------------------------------|----------------------------------|-----|
| ISSUE          | DATE         | DESCRIPTION                        |                                  |     |
| 1              | 10/20/2008   | 30% PRICING                        |                                  |     |
| 2              | 11/07/2008   | 30% DESIGN REVISION                |                                  |     |
| 3              | 12/12/2008   | 60% INTERNAL QA/QC & COST ESTIMATE |                                  |     |
| 4              | 12/19/2008   | 60% PRE-FINAL NASA REVIEW          |                                  |     |
| 5              | 02/16/2009   | 90% QA/QC & COST ESTIMATE          |                                  |     |
| MARK           | DATE         | DESCRIPTION                        |                                  |     |
| DRAWN          | J. NAGANO    | DATE                               |                                  |     |
| DESIGNED       | J. LIVERMORE | DATE                               |                                  |     |
| CHECKED        | N. SHAH      | DATE                               |                                  |     |
| PROJMR         |              | DATE                               |                                  |     |
| REQUESTOR      |              | DATE                               |                                  |     |
| RADA           |              | DATE                               |                                  |     |
| SAFETY         |              | DATE                               |                                  |     |
| SUPERVISOR     |              | DATE                               |                                  |     |
| SIZE           | CAGE CODE    | A232-0800-                         | S231                             | REV |
| D              | 25307        |                                    |                                  |     |
| SCALE          | INDEX        | SHEET                              | OF                               |     |




- NOTES:
- SEE SHEET S001 AND S002 FOR GENERAL NOTES, SYMBOLS AND ABBREVIATIONS.
  - SEE SHEETS S003 THRU S007 FOR TYPICAL DETAILS.
  - CENTERLINE OF W COLUMNS AT GRID LINE, TYPICAL UNO.
  - FOR METAL DECK SECTION PROPERTIES & WELDING REQUIREMENTS, SEE DETAIL 9 S006
  - PROVIDE 3/4"x4.5" TALL HEADED STUDS FOR ALL BEAMS AT 1'-0" O.C. TYPICAL UNO.
  - INDICATES FULL MOMENT CONNECTION PER TYPICAL DETAIL 12 S005
  - INDICATES TYPICAL MOMENT CONNECTION PER DETAIL 16 S005
  - C=3/4" INDICATES BEAM CAMBER.
  - W16x... INDICATES FULL HEIGHT SHEAR TAB PER 12 S004
  - INDICATES BOTTOM FLANGE BRACE PER TYPICAL DETAIL 6 S007, EQUALLY SPACED ALONG BEAM SPAN TYP. U.N.O.
  - INDICATES DRAG CONNECTION PER TYPICAL DETAIL 15 S004
  - CONTRACTOR TO VERIFY ALL DIMENSIONS RELATED TO ELEVATOR.
  - FOR VERTICAL BRACING ELEVATIONS, SEE SHEET S-501.
  - SEE SHEET S211 & S212 FOR COLUMN SIZES WHICH EXTEND TO FOUNDATION. COLUMNS WITH SIZES NOTED ON THIS SHEET, BEGINS ABOVE THIS FLOOR BEAM TOP OF STEEL LEVEL.
  - TOP OF STEEL ELEVATION = 26'-6" U.N.O., T.O. O.W.J.=26'-11" U.N.O.
  - OPEN WEB STEEL JOISTS SHALL BE DESIGNED IN ACCORDANCE W/ THE MINIMUM DESIGN LOADS INDICATED IN O.W.J. LOADING DIAGRAM, THIS SHEET.
  - \* INDICATES T.O.S.=26'-11"
  - FOR EDGE OF DECK DIMENSIONS, REFER TO ARCHITECTURAL DRAWINGS.



| PROJECT STATUS |              |                                    | PRELIMINARY-NOT FOR CONSTRUCTION  |            |
|----------------|--------------|------------------------------------|---|------------|
| ISSUE          | DATE         | DESCRIPTION                        |   |            |
| 1              | 10/20/2008   | 30% PRICING                        |   |            |
| 2              | 11/07/2008   | 30% DESIGN REVISION                |   |            |
| 3              | 12/12/2008   | 60% INTERNAL QA/QC & COST ESTIMATE |   |            |
| 4              | 12/19/2008   | 60% PRE-FINAL NASA REVIEW          |   |            |
| 5              | 02/16/2009   | 90% QA/QC & COST ESTIMATE          |   |            |
| MARK           | DATE         | DESCRIPTION                        |   |            |
| DRAWN          | J. NAGANO    | DATE                               |   |            |
| DESIGNED       | J. LIVERMORE | DATE                               |   |            |
| CHECKED        | N. SHAH      | DATE                               |   |            |
| PROJECT MGR    |              | DATE                               |   |            |
| REQUESTOR      |              | DATE                               |   |            |
| RADA           |              | DATE                               |   |            |
| SAFETY         |              | DATE                               |   |            |
| SUPERVISOR     |              | DATE                               |   |            |
|                |              |                                    | <div>Ames Research Center<br/>Moffet Field, California</div> <div>N232 COLLABORATIVE SUPPORT FACILITY</div> <div>PARTIAL ROOF FRAMING PLAN<br/>SOUTH WING</div> |            |
| SIZE           | D            | CAGE CODE                          | 25307   | A232-0800- |
| SCALE          |              | INDEX                              |   |            |
|                |              | SHEET                              | S232  | REV        |
|                |              | OF                                 |   |            |






1 | TYPICAL GIRDER OPENINGS  
S301 REF: SCALE: 1/4" = 1'-0"

2/16/2009 4:52:25 PM

| PROJECT STATUS |             | PRELIMINARY-NOT FOR CONSTRUCTION    |           |                                    |       |     |
|----------------|-------------|-------------------------------------|-----------|------------------------------------|-------|-----|
| ISSUE          |             |                                     |           |                                    |       |     |
| 1              | 10/20/2008  |                                     |           | 30% PRICING                        |       |     |
| 2              | 11/07/2008  |                                     |           | 30% DESIGN REVISION                |       |     |
| 3              | 12/12/2008  |                                     |           | 60% INTERNAL QA/QC & COST ESTIMATE |       |     |
| 4              | 12/19/2008  |                                     |           | 60% PRE-FINAL, NASA REVIEW         |       |     |
| 5              | 02/16/2009  |                                     |           | 90% QA/QC & COST ESTIMATE          |       |     |
| MARK           | DATE        | DESCRIPTION                         |           |                                    |       |     |
| DRAWN          | J NAGANO    | DATE                                |           |                                    |       |     |
| DESIGNED       | J LIVERMORE | DATE                                |           |                                    |       |     |
| CHECKED        | N. SHAH     | DATE                                |           |                                    |       |     |
| PROJ.MGR       | DATE        | N232 COLLABORATIVE SUPPORT FACILITY |           |                                    |       |     |
| REQUESTOR      | DATE        |                                     |           |                                    |       |     |
| R&QA           | DATE        |                                     |           |                                    |       |     |
| SAFETY         | DATE        |                                     |           |                                    |       |     |
| SUPERVISOR     | DATE        |                                     |           |                                    |       |     |
|                |             | SIZE                                | CAGE CODE | A232-0800-                         | S301  | REV |
|                |             | D                                   | 25307     |                                    |       |     |
|                |             | SCALE                               |           | INDEX                              | SHEET | OF  |






10 | BRACE CONNECTION AT ROOF

---

S501 | REF: S501


SCALE: 1/2" = 1'-0"




5 | TYPICAL BRACED FRAME ELEVATION

---


S501 REF: S211 SCALE: 3/8" = 1'-0"




14 | TYPICAL BRACE CONN AT FOUNDATION




|      |                                 |        |              |
|------|---------------------------------|--------|--------------|
| 8    | BEAM TO BEAM CONN. AT 2nd FLOOR |        |              |
| S501 | REF: S501                       | SCALE: | 1/2" = 1'-0" |




13 | COLUMN BASEPLATE  
S501 REF: S501 SCALE: 1" = 1'-0"




12 | EXTERIOR COLUMN BASEPLATE  
S501 REF: S501 SCALE: 1" = 1'-0"



## 16 | BRACE CONNECTION AT 2ND FLOOR




4 CURB FOUNDATION DETAIL  
S501 REF: S211 SCALE: 3/8" = 1'-0"

|                 |            |  |           |            |      |
|-----------------|------------|--|-----------|------------|------|
| PROJECT STATUS  |            | PRELIMINARY-NOT FOR CONSTRUCTION   |           |            |      |
| ISSUE           |            |  |           |            |      |
| 1               | 10/20/2008 | 30% PRICING  |           |            |      |
| 2               | 11/07/2008 | 30% DESIGN REVISION  |           |            |      |
| 3               | 12/12/2008 | 60% INTERNAL QA/QC & COST ESTIMATE   |           |            |      |
| 4               | 12/19/2008 | 60% PRE-FINAL, NASA REVIEW   |           |            |      |
| 5               | 02/16/2009 | 90% QA/QC & COST ESTIMATE  |           |            |      |
|                 |            |  |           |            |      |
| MARK            | DATE       | DESCRIPTION  |           |            |      |
| DRAWN           | DATE       |  <p><b>Ames Research Center</b><br/>Moffett Field, California</p> <p>N232 COLLABORATIVE SUPPORT FACILITY</p> <p><b>SECTIONS AND DETAILS</b></p> |           |            |      |
| DESIGNED        | DATE       |  |           |            |      |
| CHECKED         | DATE       |  |           |            |      |
| PROJECT MANAGER | DATE       |  |           |            |      |
| REQUESTOR       | DATE       |  |           |            |      |
| RSQA            | DATE       |  |           |            |      |
| SAFETY          | DATE       |  |           |            |      |
| SUPERVISOR      | DATE       |  |           |            |      |
|                 |            |  |           |            |      |
|                 |            |  |           |            |      |
|                 |            | SIZE   | CAGE CODE | REV        |      |
|                 |            | D  | 25307     | A232-0800- | S501 |
|                 |            | SCALE  | INDEX     | SHEET      | OF   |







|                |             |                                  |   |            |  |      |
|----------------|-------------|----------------------------------|---|------------|--|------|
| PROJECT STATUS |             | PRELIMINARY-NOT FOR CONSTRUCTION |   |            |  |      |
| ISSUE          |             |                                  |   |            |  |      |
| 1              |             | 10/20/2008                       | 30% PRICING   |            |  |      |
| 2              |             | 11/07/2008                       | 30% DESIGN REVISION   |            |  |      |
| 3              |             | 12/12/2008                       | 60% INTERNAL QA/QC & COST ESTIMATE  |            |  |      |
| 4              |             | 12/19/2008                       | 60% PRE-FINAL, NASA REVIEW  |            |  |      |
| 5              |             | 02/16/2009                       | 90% QAQC & COST ESTIMATE  |            |  |      |
| MARK           |             | DATE                             | DESCRIPTION   |            |  |      |
| DRAWN          | J NAGANO    | DATE                             | <div><div>Ames Research Center<br/>Moffet Field, California</div></div> <div>N232 COLLABORATIVE SUPPORT FACILITY</div> |            |  |      |
| DESIGNED       | J LIVERMORE | DATE                             |   |            |  |      |
| CHECKED        | N SHAH      | DATE                             |   |            |  |      |
| PROJ MGR       |             | DATE                             |   |            |  |      |
| REQUESTOR      |             | DATE                             |   |            |  |      |
| RADA           |             | DATE                             | BRACE DETAILS   |            |  |      |
| SAFETY         |             | DATE                             |   |            |  |      |
| SUPERVISOR     |             | DATE                             |   |            |  |      |
|                |             | SIZE                             | CAGE CODE   |            |  | REV  |
|                |             | D                                | 25307   | A232-0800- |  | S502 |
|                |             | SCALE                            | INDEX   | SHEET      |  | OF   |




2/16/2009 4:52:37 PM



SECTION AT RAISED SLAB ACCESS  
3 FLOOR  
S503 REF: S221 SCALE: 1/2" = 1'-0"




SECTION AT RAISED SLAB ACCESS  
2 FLOOR  
S503 REF: S221 SCALE: 1/2" = 1'-0"






SECTION AT RAISED SLAB  
1 FLOOR  
S503 REF: S221 SCALE: 1/2" = 1'-0"

| PROJECT STATUS |            |                                    | PRELIMINARY-NOT FOR CONSTRUCTION  |  |
|----------------|------------|------------------------------------|---|--|
| ISSUE          | DATE       | DESCRIPTION                        |   |  |
| 1              | 10/20/2008 | 30% PRICING                        |   |  |
| 2              | 11/07/2008 | 30% DESIGN REVISION                |   |  |
| 3              | 12/12/2008 | 60% INTERNAL QA/QC & COST ESTIMATE |   |  |
| 4              | 12/19/2008 | 60% PRE-FINAL, NASA REVIEW         |   |  |
| 5              | 02/16/2009 | 90% QA/QC & COST ESTIMATE          |   |  |
| MARK           | DATE       | DESCRIPTION                        |   |  |
| DRAWN          | Author     | DATE                               | <div><div><div></div></div><div>Ames Research Center<br/>Moffet Field, California</div></div> <div>N232 COLLABORATIVE SUPPORT FACILITY</div> <div>DETAILS</div> <div><div>SIZE</div><div>CAGE CODE</div><div>A232-0800-</div><div>S503</div><div>REV</div></div> <div><div>SCALE</div><div>INDEX</div><div>SHEET</div><div>OF</div></div> |  |
| DESIGNED       | Designer   | DATE                               |   |  |
| CHECKED        | Checker    | DATE                               |   |  |
| PROJ.MGR       |            | DATE                               |   |  |
| REQUESTOR      |            | DATE                               |   |  |
| RADA           |            | DATE                               |   |  |
| SAFETY         |            | DATE                               |   |  |
| SUPERVISOR     |            | DATE                               |   |  |






|                |              |   |  |            |  |
|----------------|--------------|---|--|------------|--|
| PROJECT STATUS |              | <h1 style="text-align: center;">PRELIMINARY NOT FOR CONSTRUCTION</h1> |  |            |  |
| ISSUE          |              |   |  |            |  |
| 1              | 10/20/2008   | 30% PRICING   |  |            |  |
| 2              | 11/07/2008   | 30% DESIGN REVISION   |  |            |  |
| 3              | 12/12/2008   | 60% INTERNAL QA/QC & COST ESTIMATE                                    |  |            |  |
| 4              | 12/19/2008   | 60% PRE-FINAL, NASA REVIEW  |  |            |  |
| 5              | 02/16/2009   | 90% QAQC & COST ESTIMATE  |  |            |  |
|                |              |   |  |            |  |
| MARK           |              | DATE  | DESCRIPTION  |            |  |
| DRAWN          | J. NAGANO    | DATE  |  <div style="text-align: center;"> <b>Ames Research Center</b><br/> Moffet Field, California </div> |            |  |
| DESIGNED       | J. LIVERMORE | DATE  |  |            |  |
| CHECKED        | N. SHAH      | DATE  |  |            |  |
| PROJ/MGR       |              | DATE  |  |            |  |
| REQUESTOR      |              | DATE  |  |            |  |
| REQ'D          |              | DATE  | <h2 style="text-align: center;">ENLARGED CANOPY PLANS AND DETAILS</h2>   |            |  |
| SAFETY         |              | DATE  |  |            |  |
| SUPERVISOR     |              | DATE  |  |            |  |
|                |              | SCALE   | SHEET  | OF         |  |
|                |              | SIZE<br>D   | CAGE CODE<br>25307   | A232-0800- | <div style="font-size: 2em; font-weight: bold;">S601</div> |
|                |              | SCALE   | INDEX  | SHEET      | OF   |







2/16/2009 4:52:41 PM




14 | WING WALL FOOTING SECTION  
S701 REF: S211 SCALE: 1/2" = 1'-0"




10 | SCREEN WALL PERPENDICULAR TO BEAM  
S701 REF: SCALE: 1" = 1'-0"




13 | HSS CONNECTION TO HSS POST  
S701 REF: S701 SCALE: 1 1/2" = 1'-0"




16 | HSS CONNECTION DETAIL  
S701 REF: SCALE: 1 1/2" = 1'-0"



12 | HSS TO HSS CONN. DETAIL  
S701 REF: S701 SCALE: 1 1/2" = 1'-0"



8 | SCREEN WALL PARALLEL TO BEAM  
S701 REF: SCALE: 1" = 1'-0"



1 | WING WALL FRAMING ELEVATION  
S701 REF: S211 SCALE: 3/8" = 1'-0"

| PROJECT STATUS |             |                                    | PRELIMINARY-NOT FOR CONSTRUCTION |           |          |
|----------------|-------------|------------------------------------|----------------------------------|-----------|----------|
| ISSUE          | DATE        | DESCRIPTION                        |                                  |           |          |
| 1              | 10/20/2008  | 30% PRICING                        |                                  |           |          |
| 2              | 11/07/2008  | 30% DESIGN REVISION                |                                  |           |          |
| 3              | 12/12/2008  | 60% INTERNAL QA/QC & COST ESTIMATE |                                  |           |          |
| 4              | 12/19/2008  | 60% PRE-FINAL, NASA REVIEW         |                                  |           |          |
| 5              | 02/16/2009  | 90% QA/QC & COST ESTIMATE          |                                  |           |          |
| MARK           | DATE        | DESCRIPTION                        |                                  |           |          |
| DRAWN          | J NAGANO    |                                    |                                  |           |          |
| DESIGNED       | J LIVERMORE |                                    |                                  |           |          |
| CHECKED        | N SHAH      |                                    |                                  |           |          |
| PROJ MGR       |             |                                    |                                  |           |          |
| REQUESTOR      |             |                                    |                                  |           |          |
| RADA           |             |                                    |                                  |           |          |
| SAFETY         |             |                                    |                                  |           |          |
| SUPERVISOR     |             |                                    |                                  |           |          |
|                |             |                                    | SIZE                             | CAGE CODE | REV      |
|                |             |                                    | D                                | 25307     | S701     |
|                |             |                                    | SCALE                            | INDEX     | SHEET OF |