

NN611409107 Q - Attachment A  
NASA Goddard Space Flight Center

Area 200 Tree Cutting - Statement of Work

A 5.77 acre area has been flagged in the field for tree cutting (see attached maps).

The contractor shall complete the described work within **30 calendar days** of award.

The Tree Removal Contractor shall:

- Cut all trees in the designated area at a maximum height of 12" above the ground.
- Not grub the stump nor root ball or create any unnecessary soil disturbance .
- Either remove the tree material from the site or chip the material and spread it evenly over the ground..
- Comply with the attached "Standard Erosion and Sediment Control Plan for forest harvest Operations" during all phases of the work.
- Leave the site stabilized in accordance with the attached Plan and leave all paved surfaces clean.
- Comply with all applicable Federal, State and local laws, regulations, ordinances, and orders relating to safety and health.
- Submit a Safety Plan which describes the likely unique hazards to be encountered and the methods mitigate the hazards and obtain safety objectives.

The site is a secured government facility. Workers shall obtain NASA temporary badges and shall be US citizens.

NASA Technical Point of Contract: Jim Long, 301-286-9836